

SCHEDULE OF QUANTITIES

#2001409 IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3, SPECIAL

EACH	LOCATION		
	I-80		
1	RT	216 + 27.92	STAGE III
1	LT	219 + 44.41	STAGE III
2	TOTAL		

20200100 EARTH EXCAVATION

CU YD	LOCATION		
	I-80		
366	RT	205 + 09 - 216 + 00	
143	LT	212 + 75 - 216 + 00	
476	LT	219 + 50 - 230 + 50	
138	RT	219 + 50 - 222 + 50	
1,123			

25000210 SEEDING, CLASS 2A

ACRE	LOCATION		
	I-80		
0.35	RT	205 + 09 - 216 + 00	
0.45	LT	212 + 75 - 216 + 00	
0.58	LT	219 + 50 - 230 + 50	
0.32	RT	219 + 50 - 222 + 50	
1.75			

25100630 EROSION CONTROL BLANKET

SQ YD	LOCATION		
	I-80		
1,694	RT	205 + 09 - 216 + 00	
2,178	LT	212 + 75 - 216 + 00	
2,807	LT	219 + 50 - 230 + 50	
1,549	RT	219 + 50 - 222 + 50	
8,228			

28000250 TEMPORARY EROSION CONTROL SEEDING

POUND	LOCATION		
	I-80		
210	RT	205 + 09 - 216 + 00	
270	LT	212 + 75 - 216 + 00	
348	LT	219 + 50 - 230 + 50	
192	RT	219 + 50 - 222 + 50	
1,020			

25000750 MOWING

ACRE	LOCATION		
	I-80		
0.35	RT	205 + 09 - 216 + 00	
0.45	LT	212 + 75 - 216 + 00	
0.58	LT	219 + 50 - 230 + 50	
0.32	RT	219 + 50 - 222 + 50	
1.75			

28000400 PERIMETER EROSION BARRIER

FOOT	LOCATION		
	I-80		
975	RT	206 + 25 - 216 + 00	
245	RT	214 + 30 - 216 + 75	
350	LT	213 + 00 - 216 + 50	
250	LT	219 + 00 - 221 + 50	
600	LT	222 + 00 - 228 + 00	
325	RT	219 + 25 - 222 + 50	
2,745			

31100910 SUB-BASE GRANULAR MATERIAL, TYPE A 12"

SQ YD	LOCATION			
	I-80			
1,077	RT	205 + 09.04 - 213 + 51.89	10' Shoulder	
423	LT	212 + 90.13 - 215 + 96.16	10' Shoulder	
220	RT	213 + 51.89 - 215 + 24.34	10' Shoulder	
260	RT	214 + 16.82 - 216 + 26.30	10' Shoulder (Ramp)	
279	LT	219 + 44.46 - 221 + 46.29	10' Shoulder (Ramp)	
366	RT	219 + 66.25 - 222 + 43.92	10' Shoulder	
201	LT	220 + 51.90 - 222 + 32.96	10' Shoulder	
1,049	LT	222 + 32.96 - 230 + 31.58	10' Shoulder	
3,875	TOTAL			

31200500 STABILIZED SUBBASE - HOT-MIX ASPHALT, 4"

SQ YD	LOCATION			
	I-80			
246	LT	215 + 96.16 - 216 + 39.44	CRC Pavement	
265	RT	216 + 26.11 - 216 + 69.18	CRC Pavement	
304	LT	218 + 94.64 - 219 + 43.38	CRC Pavement	
244	RT	219 + 22.97 - 219 + 66.32	CRC Pavement	
1,060	TOTAL			

40300200 BITUMINOUS MATERIALS (PRIME COAT)

TON	LOCATION			
	I-80			
0.6	RT	205 + 09.04 - 213 + 51.89	10' Shoulder	
0.2	LT	212 + 90.13 - 215 + 96.16	10' Shoulder	
0.7	LT	213 + 24.14 - 215 + 96.16	Mainline	
0.1	LT	213 + 24.14 - 215 + 96.16	6' Shoulder	
0.6	RT	213 + 51.89 - 215 + 24.34	10' Shoulder	
0.1	RT	213 + 51.85 - 216 + 26.12	6' Shoulder	
0.7	RT	213 + 51.85 - 216 + 26.12	Mainline & Ramp	
0.1	RT	214 + 04.24 - 215 + 24.83	4' Shoulder (Ramp)	
0.1	RT	214 + 16.82 - 216 + 26.30	10' Shoulder (Ramp)	
1.6	LT	219 + 44.46 - 221 + 46.29	10' Shoulder (Ramp)	
0.7	LT	219 + 43.38 - 222 + 33.26	Mainline & Ramp	
0.1	LT	219 + 43.38 - 222 + 33.26	6' Shoulder	
0.2	RT	219 + 66.25 - 222 + 43.92	10' Shoulder	
0.7	RT	219 + 66.33 - 222 + 45.33	Mainline	
0.1	RT	219 + 66.33 - 223 + 45.33	6' Shoulder	
0.1	LT	220 + 51.90 - 222 + 32.96	10' Shoulder	
0.6	LT	222 + 32.96 - 230 + 31.58	10' Shoulder	
7.4	TOTAL			