

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
316	102T	LEE	41	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

Code No.	Item	Units	Total Quantity	RURAL 80 % Fed. 20 % State Y007
54010603	PRECAST CONCRETE BOX CULVERT 6' X 3'	FOOT	122	122
54215550	METAL END SECTIONS 15"	EACH	2	2
5421D024	PIPE CULVERTS, CLASS D, TYPE 1 24" (TEMPORARY)	FOOT	26	26
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	52	52
63301210	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	325	325
63301990	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1	EACH	2	2
63302700	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	2
63304385	TRAFFIC BARRIER TERMINAL REMOVAL, TYPE 1	EACH	2	2
63500105	DELINEATORS	EACH	4	4
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	19	19
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	2	2
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4
67100100	MOBILIZATION	L SUM	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	15	15
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	63	63
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	21	21
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	6,520	6,520
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	10	10
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2
X0323660	DROP BOX NO.1	EACH	1	1
XX001135	PAVEMENT PATCHING SPECIAL	SQ YD	182	182
Z0005400	BREAKER-RUN CRUSHED STONE	TON	306	306
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
Z0023600	FILLING EXISTING CULVERTS	EACH	2	2
* SPECIALTY ITEMS				
● NON- PARTICIPATING ITEMS				

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. DRAWN BY
 HORIZ. CHECKED BY
 DATE

PLOT DATE = Thu Jan 24 15:17:37 2008
 FILE NAME = C:\Programs\p200807\dl080807.dwg
 PLOT SCALE = 50.0000 / IN.
 USER NAME = hennicke