SCHEDULE OF QUANTITIES

54010603 PRECAST CONCRETE BOX CULVERT 6' X 3'

FOOT	LOCATION	
61	457 + 83	RT
61	457 + 83	LT
122	TOTAL	

54215550 METAL END SECTIONS 15"

EACH	LOCATION	
2	424 + 19	RT & LT
2	TOTAL	

5421D024 PIPE CULVERTS, CLASS D, TYPE 1 24" (TEMPORARY)

FOOT	LOCATION	
13	457 + 83	LT
13	457 + 83	LT
26	TOTAL	

542D0220 PIPE CULVERTS, CLASS D, TYPE 1 15"

FOOT	LOCATION	
52	424 + 19	RT
52	TOTAL	

63301210 REMOVE AND RE-ERECT STEEL PLATE BEAM GUARD RAIL TYPE A

FOOT	LOCATION	
125	422 + 1.75 - 423 + 26.75	RT
200	422 + 1.75 - 424 + 1.75	LT
325	TOTAL	

63301990 REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1

EACH	LOCATION	
1	447 + 7.00	RT
1	447 + 7.00	LT
2	TOTAL	

63302700 REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 6

EACH	LOCATION	
1	421 + 55.50 - 422 + 1.75	RT
1	421 + 55.50 - 422 + 1.75	LT
2	TOTAL	

63304385 TRAFFIC BARRIER TERMINAL REMOVAL, TYPE 1

EACH	LOCATION	
1	423 + 33.00	LT
1	424 + 37.00	LT
2	TOTAL	

63500105 DELINEATORS

EACH	LOCATION	
1	423 + 75.00	RT
1	424 + 52.00	LT
1	457 + 74.00	RT
1	457 + 91.00	LT
4	TOTAL	

66600105 FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS

EACH	LOCATION	
2	420 + 00	RT & LT
2	421 + 00	RT & LT
1	423 + 00	RT
1	424 + 00	RT
1	426 + 00	LT
2	431 + 00	RT & LT
2	432 + 00	RT & LT
2	455 + 00	RT & LT
2	457 + 50.00	RT & LT
2	458 + 25.00	RT & LT
2	460 + 00	RT & LT
19	TOTAL	

66700305 PERMANENT SURVEY MARKERS, TYPE II

EACH	LOCATION
2	Location to be determined out in field.
2	TOTAL

70300100 SHORT-TERM PAVEMENT MARKING

FOOT	LOCATION		
21.0	457 + 51.50 - 458 + 14.5	RT	TEMP PATCH
21.0	457 + 51.50 - 458 + 14.5	RT	PERM PATCH
21.0	457 + 51.50 - 458 + 14.5	RT	SURFACE
63	TOTAL		

70301000 WORK ZONE PAVEMENT MARKING REMOVAL

SQ FT	LOCATION		
7.0	457 + 51.50 - 458 + 14.5	RT	TEMP PATCH
7.0	457 + 51.50 - 458 + 14.5	RT	PERM PATCH
7.0	457 + 51.50 - 458 + 14.5	RT	SURFACE
21	TOTAL		

78001110 PAINT PAVEMENT MARKING - LINE 4"

FOOT	LOCATION	
1045	421 + 55.0 - 432 + 00	RT
270	421 + 55.0 - 432 + 00	CL
1045	421 + 55.0 - 432 + 00	LT
400	455 + 00 - 459 + 00	RT
100	455 + 00 - 459 + 00	CL
400	455 + 00 - 459 + 00	LT
3260	TOTAL 6520 is two coats	

78200410 GUARDRAIL MARKERS, TYPE A

EACH	LOCATION	
5	421 + 55.0 - 423 + 75	RT
5	421 + 55.0 - 424 + 52	LT
10	TOTAL	

78201000 TERMINAL MARKER - DIRECT APPLIED

EACH	LOCATION	
1	423 + 75.00	RT
1	424 + 52.00	LT
2	TOTAL	

X0323660 DROP BOX NO.1

EACH	LOCATION	
1	457 + 83.0	LT
1	TOTAL	

XX001135 PAVEMENT PATCHING SPECIAL

SQ YD	LOCATION	
91.0	457 + 51.50 - 458 + 14.5	RT
91.0	457 + 51.50 - 458 + 14.5	LT
182.0	TOTAL	

Z0005400 BREAKER-RUN CRUSHED STONE

TON	LOCATION
306	457 + 83.0
306	TOTAL

Z0023600 FILLING EXISTING CULVERTS

EACH	LOCATION
1	430 + 99.0
1	430 + 85.0
2	TOTAL

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. HORIZ.

DRAWN BY

DATE

CHECKED BY

PLOT DATE = Wed Jan 30 09:09:09 2008
FILE NAME = c:\pwworking\d06\d0577\d0577ov1.dgn
PLOT SCALE = 50.0000 ' / in.
USER NAME = hemsonke