

CODE NUMBER	ITEM	UNIT	SN 008-0029	SN 008-0030	X081-2A
					100% STATE TOTAL QUANTITY
50300300	PROTECTIVE COAT	SQ YD	36.3	99.4	13
50102400	CONCRETE REMOVAL	CU YD	3.0	15.7	18.7
50300255	CONCRETE SUPERSTRUCTURE	CU YD	2.7	14.1	16.8
50300260	BRIDGE DECK GROOVING	SQ YD	26.9		26.9
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQ FT	258	435	693
50400505	PRECAST PRESTRESSED CONCRETE DECK BEAMS (27" DEPTH)	SQ FT		190	190
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	672	3089	3761
51500100	NAME PLATES	EACH	1	1	2
63302700	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	1	2	3
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	2	2	4
67100100	MOBILIZATION	L SUM	0.5	0.5	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1	2
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	2
70106700	TEMPORARY RUMPLE STRIP	EACH	6	6	12
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	1138	2818	3956
70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	26	26	52
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	431	991	1422
70400100	TEMPORARY CONCRETE BARRIER	FOOT	162.5	312.5	475
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT		275	275
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	2373	3173	5546
* 78200500	BARRIER WALL MARKERS	EACH	5	19	24
78300100	PAVEMENT MARKING REMOVAL	SQ FT	48	59	107
X0320047	REMOVAL OF EXISTING PRECAST PRESTRESSED CONCRETE DECK BEAMS	SQ FT	258	634	892
X0321781	MECHANICAL SPLICE	EACH	33	333	366
X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	26.9	69.5	96.4
XZ191600	SILICONE BRIDGE JOINT SEALANT	FOOT		3	3
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH		2	2
Z0013798	CONSTRUCTION LAYOUT	L SUM	0.5	0.5	1
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON - REDIRECTIVE), TEST LEVEL 3	EACH	2	2	4
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON - REDIRECTIVE), TEST LEVEL 3	EACH		2	2

*SPECIALTY ITEMS

FILE NAME = c:\projects\p206807\d06807cwr.dgn	USER NAME = duncenfa	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE. 17	SECTION *	COUNTY CARROLL	TOTAL SHEETS 27	SHEET NO. 2
PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -	SCALE:					SHEET NO. 2 OF 27 SHEETS	STA.	TO STA.	CONTRACT NO. 64D28	
PLOT DATE = Fri Jan 25 13:43:55 2008	DATE -	REVISED -	FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT							
• (4BR-2D) & (4BR-1D)												