

63302700 REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 6

EACH	LOCATION		
	US 52/IL 64		
	SN 008-0029		
1	LT	673+23.8 -	673+67.58
	SN 008-0030		
1	LT	743+13.4 -	743+57.15
1	RT	744+72.0 -	744+94.38
<u>3</u>	TOTAL		

70106700 TEMPORARY RUMPLE STRIP

EACH	LOCATION		
	US 52/IL 64		
	SN 008-0029		
1	RT	648+50	STAGE I
1	RT	658+50	STAGE I
1	RT	663+50	STAGE I
1	LT	683+19	STAGE I
1	LT	688+19	STAGE I
1	LT	693+19	STAGE I
	SN 008-0030		
1	RT	723+76	STAGE I
1	RT	728+76	STAGE I
1	RT	733+76	STAGE I
1	LT	754+79	STAGE I
1	LT	759+80	STAGE I
1	LT	764+81	STAGE I
<u>12</u>	TOTAL		

70300520 PAVEMENT MARKING TAPE TYPE III, 4"

FOOT	LOCATION			
	US 52/IL 64			
	SN 008-0029			
1,138	LT & RT	670+50.0 -	676+19.00	STAGE I White Edge Line
	SN 008-0030			
1,411	LT & RT	740+75.8 -	747+81.3	STAGE I White Edge Line
1,407	LT & RT	740+75.9 -	747+79.30	STAGE II White Edge Line
<u>3,956</u>	TOTAL			

70300570 PAVEMENT MARKING TAPE TYPE III, 24"

FOOT	LOCATION			
	US 52/IL 64			
	SN 008-0029			
13	RT	670+50.0	STAGE I	White Stop Bar
13	LT	676+18.0	STAGE I	White Stop Bar
	SN 008-0030			
13	RT	740+75.9	STAGE I	White Stop Bar
13	LT	747+79.3	STAGE I	White Stop Bar
<u>52</u>	TOTAL			

70301000 WORKZONE PAVEMENT MARKING REMOVAL

SQ. FT.	LOCATION			
	US 52/IL 64			
	SN 008-0029			
26	RT	670+50.0	STAGE I	White Stop Bar
379	LT & RT	670+50.0 -	676+19.00	STAGE I White Edge Line
26	LT	676+18.0	STAGE I	White Stop Bar
	SN 008-0030			
26	RT	740+75.9	STAGE II	White Stop Bar
470	LT & RT	740+75.8 -	747+81.3	STAGE I White Edge Line
469	LT & RT	740+75.9 -	747+79.30	STAGE II White Edge Line
26	LT	747+79.3	STAGE II	White Stop Bar
<u>1,422</u>	TOTAL			

70400100 TEMPORARY CONCRETE BARRIER

FOOT	LOCATION			
	US 52/IL 64			
	SN 008-0029			
162.5	LT	673+05.8 -	674+68.38	STAGE I
	SN 008-0030			
312.5	RT	742+46.9 -	745+59.25	STAGE I
<u>475</u>	TOTAL			

70400200 RELOCATE TEMPORARY CONCRETE BARRIER

FOOT	LOCATION			
	US 52/IL 64			
	SN 008-0030			
275	LT	742+71.81 -	745+76.70	STAGE II
<u>275</u>	TOTAL			

78001110 PAINT PAVEMENT MARKING - LINE 4" (TWO COATS)

FOOT	LOCATION			
	US 52/ IL 64			
	SN 008-0029			
260	STA.	670+48.1 -	676+20.97	Yellow Skip Dash
2113	LT & RT	670+48.1 -	676+20.97	White Edge Line
	SN 008-0030			
360	STA.	740+73.9 -	747+81.3	Solid Yellow
2813	LT & RT	740+73.9 -	747+81.3	Yellow Skip Dash
<u>5547</u>	TOTAL			White Edge Line

78200500 BARRIER WALL MARKERS

EACH	LOCATION			
	US 52/ IL 64			
	SN 008-0029			
1	LT	673+68.4 -	673+91.56	STAGE I PARAPET WALL
4	LT	673+40.4 -	674+28.00	STAGE I TEMP WALL
	SN 008-0030			
3	RT	743+84.8 -	744+47.69	STAGE I PARAPET WALL
7	LT	743+21.8 -	744+84.32	STAGE I TEMP WALL
2	LT	743+57.8 -	744+07.87	STAGE II PARAPET WALL
7	LT	743+21.8 -	744+82.34	STAGE II TEMP WALL
<u>24</u>	TOTAL			

78300100 PAVEMENT MARKING REMOVAL

SQ. FT.	LOCATION			
	US 52/ IL 64			
	SN 008-0029			
48	STA.	670+48.1 -	676+20.97	STAGE I Yellow Skip Dash
	SN 008-0030			
59	STA.	740+73.9 -	747+81.3	STAGE I Yellow Skip Dash
<u>107</u>	TOTAL			

Z0030250 IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3

EACH	LOCATION			
	US 52/ IL 64			
	SN 008-0029			
1	LT	673+05.87	STAGE I	
1	LT	674+68.38	STAGE I	
	SN 008-0030			
1	RT	742+46.93	STAGE I	
1	RT	745+59.25	STAGE I	
<u>4</u>	TOTAL			

Z0030350 IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3

EACH	LOCATION			
	US 52/ IL 64			
	SN 008-0030			
1	LT	742+71.81	STAGE II	
1	LT	745+46.70	STAGE II	
<u>2</u>	TOTAL			