

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FAU 2503	(35)BR-2	KENDALL	129	4
FED. ROAD DIST. NO.		FED. ROAD DIST. NO.	FED. ROAD DIST. NO.	

SUMMARY OF QUANTITIES

CODE #	ITEM	UNITS	URBAN QUANTITY	1000-2A	X081-2A	SFTY-1B
				ROADWAY 80% FEDERAL 20% STATE	EX SN 047-0034 PR SN 047-0062 80% FEDERAL 20% STATE	NEW SIDEWALK 50% STATE 50% VILLAGE
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	122		122	
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	192		192	
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3		
60219540	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	1	1		
60221700	MANHOLES, TYPE A, 5' DIAMETER, TYPE 8 GRATE	EACH	3	3		
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	2	2		
60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	6	6		
60240301	INLETS, TYPE B, TYPE 8 GRATE	EACH	1	1		
60240328	INLETS, TYPE B, TYPE 24 FRAME AND GRATE	EACH	2	2		
60255500	MANHOLES TO BE ADJUSTED	EACH	3	3		
60257000	MANHOLES TO BE RECONSTRUCTED	EACH	1	1		
60266600	VALVE BOX TO BE ADJUSTED	EACH	1	1		
60500040	REMOVING MANHOLES	EACH	2	2		
60500050	REMOVING CATCH BASINS	EACH	5	5		
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	1025	1025		
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	12.5	12.5		
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	2		
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2		
63200310	GUARDRAIL REMOVAL	FOOT	399	399		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	10	10		
67100100	MOBILIZATION	L SUM	1	1		
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1		
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6	6		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	456	456		
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	9696	9696		
70300645	TEMPORARY PAINT PAVEMENT MARKING LINE 12"	FOOT	326	326		
70300660	TEMPORARY PAINT PAVEMENT MARKING LINE 24"	FOOT	49	49		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3807	3807		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	260	260		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	260	260		
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	2891	2891		
* 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	68	68		
* 78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	133	133		
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	326	326		
* 78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	49	49		

* - SPECIALTY ITEMS

SUMMARY OF QUANTITIES

CODE #	ITEM	UNITS	URBAN QUANTITY	1000-2A	X081-2A	SFTY-1B
				ROADWAY 80% FEDERAL 20% STATE	EX SN 047-0034 PR SN 047-0062 80% FEDERAL 20% STATE	NEW SIDEWALK 50% STATE 50% VILLAGE
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	35	35		
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	8	8		
* 78200400	GUARDRAIL REFLECTORS	EACH	5	5		
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	44	44		
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1129	1129		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	16	16		
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	1133		1133	
XX002155	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 3V FRAME AND GRATE	EACH	2	2		
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	24		24	
Z0030030	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2	2		
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2	2		
Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	2	2		
* Z0065000	SETTING PILES IN ROCK	EACH	16		16	

* - SPECIALTY ITEMS

HAMPTON, LENZINI & RENWICK, INC.
CIVIL & STRUCTURAL ENGINEERS

HLR

3085 STEVENSON DRIVE, SUITE 201
SPRINGFIELD, ILLINOIS 62703
(217) 546-3400

ELGIN • SPRINGFIELD

PROJECT NUMBER: 12-06-0029-i DATE: 06/01/07
DESIGNED: LFS CHECKED: DRAWN: TWK

SUMMARY OF QUANTITIES
SECTION (35) BR-2
IL 25 OVER WAUBONSEE CREEK
KENDALL COUNTY

P:\07 - 247E - 1/3/2003 FILE NAME: P:\12\12052623\road\Phase II\052623\sr-t-summary-1.dgn