

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FAU 2503	(35)BR-2	KENDALL	129	6
FED. ROAD DIST. NO.	FED. AID PROJECT			
5				

ROADWAY SCHEDULE

LOCATION	HOT-MIX ASPHALT SURF CSE MIX D N70	HOT-MIX ASPHALT BINDER CSE IL-19.0 N-70	LEVELING BINDER MACHINE METHOD N70	HOT-MIX ASPHALT BASE CSE.	HOT-MIX ASPHALT BASE CSE.	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE PRIME COAT	HOT-MIX ASPHALT SURFACE REMOVAL	TEMPORARY RAMP	PAVEMENT REMOVAL	AGGREGATE FOR TEMPORARY ACCESS (ESTIMATED)	INCIDENTAL HOT-MIX ASPHALT SURFACING	BRIDGE APPROACH PAVEMENT	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	PROTECTIVE COAT	SUN-BASE GRANULAR MATERIAL TYPE A 12"	PORTLAND CEMENT CONCRETE PAVEMENT 11"
	1.5" MIN TON	1 3/4" MIN TON	1" MIN TON	10" SQ YD	6" SQ YD	GAL	TON	SQ YD	SQ YD	SQ YD	TONS	TONS	SQ. YD.	SQ. YD.	SQ YD	SQ YD	SQ YD
PRE-STAGE 1																	
STA7+18 STA 16+00				442		166	3		60		50	14				260	145
STAGE 1																	
STA7+18 STA 16+00				126					112	80	50		158	32	158		
STAGE 2																	
STA7+18 STA 16+00					75				93	559			144	28	144		
STAGE 3																	
STA7+18 STA 16+00	191	36	225			247	5	1180	148	209					661		
STONE GATE DRIVE						17	0.3	60	19			42					
NORTH ST						16	0.3	44	36			39					
TOTAL	191	36	225	568	75	446	8.6	1284	468	848	100	95	302	60	963	260	145

* ESTIMATED QUANTITY FOR BIDDING PURPOSES

P:07.DAT 11/31/2006 FILE NAME: FAU1250300230.dwg PLOT DATE: 11/06/07 11:06:07 AM

HAMPTON, LENZINI & RENWICK, INC.
 CIVIL & STRUCTURAL ENGINEERS

3085 STEVENSON DRIVE, SUITE 201
 SPRINGFIELD, ILLINOIS 62703
 (217) 546-3400

ELGIN • SPRINGFIELD

PROJECT NUMBER: 12-06-0029-1 DATE: 06/07
 DESIGNED: LFS CHECKED: DRAWN: TWK

SCHEDULE OF QUANTITIES
 SECTION (35) BR-2
 IL 25 OVER WAUBONSEE CREEK
 KENDALL COUNTY