

ROUTE NO. FAU 2503	SECTION (35)BR-2	COUNTY KENDALL	SHEET NO. 129	SHEET 9
FED. ROAD DIST. NO. 5		FED. AID PROJECT		

PAVEMENT MARKING SCHEDULE

LOCATION	PERMANENT PAVEMENT MARKINGS																	SHORT TERM PAVEMENT MARKING	PAVEMENT MARKING REMOVAL	WORK ZONE PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	LOCATION	
	POLYUREA PAVEMENT MARKING, TYPE 1																								
	PAINT PAVEMENT MARKING																								
	SOLID SINGLE WHITE 4" LINE	SOLID SINGLE WHITE 8" LINE	SOLID SINGLE WHITE 24" LINE	SOLID SINGLE WHITE 12" DIAGONAL	SKIP DASH YELLOW 6" LINE	SOLID SINGLE YELLOW 4" LINE	SOLID DOUBLE YELLOW 4" LINE	SOLID SINGLE YELLOW DIAGONAL 12" LINE	SOLID SINGLE WHITE 4" LINE	SOLID SINGLE WHITE 24" LINE	DOTTED SINGLE WHITE 4" LINE	SOLID SINGLE WHITE DIAGONAL 12" LINE	SKIP DASH YELLOW 4" LINE	SOLID SINGLE YELLOW 4" LINE	SOLID DOUBLE YELLOW 4" LINE	SOLID SINGLE YELLOW DIAGONAL 12" LINE	SKIPPED-DASHED YELLOW CENTERLINE 4"								FOOT
PRE-STAGE 1																									PRE-STAGE 1
CL. STA 7+18 TO 11+00																	108		36						CL. STA 7+18 TO 11+00
CL. STA 13+50 TO 15+00																	150		50						CL. STA 13+50 TO 15+00
CL. STA 12+50 TO 16+00																						16			CL. STA 12+50 TO 16+00
STAGE 1																									STAGE 1
RT. STA 7+18 TO 16+00										882								257	294						RT. STA 7+18 TO 16+00
CL. STA 7+18 TO 16+00															1800			608	600						CL. STA 7+18 TO 16+00
LT. STA 8+22 TO 16+00										778								264	259						LT. STA 8+22 TO 16+00
STAGE 2																									STAGE 2
RT. STA 8+12 TO 16+00										788													263		RT. STA 8+12 TO 16+00
CL. STA 8+12 TO 16+00															1576				525						CL. STA 8+12 TO 16+00
LT. STA 8+22 TO 16+00										778									259						LT. STA 8+22 TO 16+00
STAGE 3																									STAGE 3
CL. STA 7+18 TO 16+00																	198		66						CL. STA 7+18 TO 16+00
FINAL STAGE																									FINAL STAGE
RT. STA 6+88 TO 9+74	286																								RT. STA 7+18 TO 6+00
LT. STA 6+88 TO 7+18	30																								LT. STA 7+18 TO 6+00
CL. STA 6+88 TO 9+60					68											115			38						CL. STA 7+18 TO 9+60
CL. STA 8+00 TO 9+60						160									160				53						CL. STA 8+00 TO 9+60
CL. STA 9+60 TO 10+80							240											240	80						CL. STA 9+60 TO 10+80
LCL. STA 10+80 TO 16+00							1040											1040	347						LCL. STA 10+80 TO 16+00
RCL. STA 10+80 TO 15+12							864											864	288						RCL. STA 10+80 TO 15+12
CL. STA 10+80 TO 15+12								208											208						CL. STA 10+80 TO 15+12
RT. STA 11+46 TO 14+17	271			118					542			118							299						RT. STA 11+46 TO 14+17
RT. STA 13+80 TO 15+12		33									33								11						RT. STA 13+80 TO 15+12
RT. STA 15+12 TO 16+12		100							100										33						RT. STA 15+12 TO 16+12
CL. STA 7+18 TO 12+00																						20			CL. STA 7+18 TO 12+00
CL. STA 14+00 TO 16+00																						15			CL. STA 14+00 TO 16+00
CL. STA 12+40 TO 13+60																							8		CL. STA 12+40 TO 13+60
CL. 300+23 STONE GATE DR			26							26													52		CL. 300+23 STONE GATE DR
CL. 399+77 NORTH ST			23							23													46		CL. 399+77 NORTH ST
TOTAL	587	133	49	118	68	160	2144	208	3868	49	33	118	115	160	5520	208	456	1129	3807	35	8	16			

HAMPTON, LENZINI & RENWICK, INC.
 CIVIL & STRUCTURAL ENGINEERS

3085 STEVENSON DRIVE, SUITE 201
 SPRINGFIELD, ILLINOIS 62703
 (217) 546-3400

ELGIN • SPRINGFIELD

PROJECT NUMBER: 12-06-0029-1 DATE: 06/01/07
 DESIGNED: LFS CHECKED: DRAWN: TWK

SCHEDULE OF QUANTITIES
 SECTION (35) BR-2
 IL 25 OVER WAUBONSEE CREEK
 KENDALL COUNTY

PLOT DATE: 1/23/2008 FILE NAME: P:\12-06-0029\12-06-0029-1\12-06-0029-1\12-06-0029-1.dgn