

SUMMARY OF QUANTITIES				
CODE NO.	SUMMARY OF QUANTITIES PAY ITEM	UNIT	TOTAL QUANTITY	STRUCTURE S.N. 088-0029 80% FEDERAL 20% STATE
				CONSTRUCTION TYPE CODE X081-2A
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	184	184
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	85	85
20200100	EARTH EXCAVATION	CU YD	505	505
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	70	70
20400100	BORROW EXCAVATION	CU YD	125	125
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1095	1095
25000100	SEEDING, CLASS 1	ACRE	0.23	0.23
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	20	20
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	20	20
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	20	20
25100630	EROSION CONTROL BLANKET	SQ YD	854	854
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	90	90
28000300	TEMPORARY DITCH CHECKS	EACH	8	8
28000400	PERIMETER EROSION BARRIER	FOOT	1131	1131
28100107	STONE RIPRAP, CLASS A4	SQ YD	617	617
28200200	FILTER FABRIC	SQ YD	617	617
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	164	164
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	64	64
40600300	AGGREGATE (PRIME COAT)	TON	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	133	133
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	71	71
44000100	PAVEMENT REMOVAL	SQ YD	98	98
44000400	GUTTER REMOVAL	FOOT	295	295
44002500	GUTTER OUTLET REMOVAL	EACH	2	2
48101200	AGGREGATE SHOULDERS, TYPE B	TON	15	15
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	305	305
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1
50200100	STRUCTURE EXCAVATION	CU YD	18.3	18.3
50300225	CONCRETE STRUCTURES	CU YD	31.9	31.9
50300260	BRIDGE DECK GROOVING	SQ YD	213	213
50300300	PROTECTIVE COAT	SQ YD	228	228
X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	218.4	218.4

SUMMARY OF QUANTITIES				
CODE NO.	SUMMARY OF QUANTITIES PAY ITEM	UNIT	TOTAL QUANTITY	STRUCTURE S.N. 088-0029 80% FEDERAL 20% STATE
				CONSTRUCTION TYPE CODE X081-2A
50400505	PRECAST PRESTRESSED CONCRET DECK BEAMS (27" DEPTH)	SQ FT	1965	1965
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	7410	7410
*50901050	STEEL RAILING, TYPE SM	FOOT	126	126
51201600	FURNISHING STEEL PILES HP 12X53	FOOT	329	329
51202305	DRIVING PILES	FOOT	329	329
51203600	TEST PILE STEEL HP 12X53	EACH	1	1
51500100	NAME PLATES	EACH	1	1
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	73	73
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	2	2
58700300	CONCRETE SEALER	SQ FT	399	399
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	9.7	9.7
*63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	37.5	37.5
*63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4
*63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4
63200310	GUARDRAIL REMOVAL	FOOT	327	327
66500105	WOVEN WIRE FENCE, 4'	FOOT	171	171
66502300	WOVEN WIRE FENCE REMOVAL	FOOT	189	189
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	1	1
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4
67100100	MOBILIZATION	L SUM	1	1
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	1
*78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	632	632
*78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	79	79
*78200410	GUARDRAIL MARKERS, TYPE A	EACH	8	8
*78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4
X0301512	GUARDRAIL AGGREGATE EROSION CONTROL	TON	53	53
Z0000100	ABANDON EXISTING CULVERT	EACH	1	1
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1

*SPECIALTY ITEM

SUMMARY OF QUANTITIES
OSCEOLA RD. OVER SPOON RIVER TRIB.
F.A.S. ROUTE 2244 - SECTION (107B)BR
STARK COUNTY
STA. 85+31.81
S.N. 088-0017(E) S.N. 088-0029(P)