

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	(39B)I	McDONOUGH	38	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES				ROADWAY FAP 310 80% FEDERAL 20% STATE	STRUCTURE SN.055-0005 80% FEDERAL 20% STATE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
				1000-2A	X080-2A
20200100	EARTH EXCAVATION	CU YD	105	105	
20400800	FURNISHED EXCAVATION	CU YD	321	321	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	797	797	
25000300	SEEDING, CLASS 3	ACRE	0.16	0.16	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	14	14	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	14	14	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	14	14	
25100630	EROSION CONTROL BLANKET	SQ YD	774	774	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	16	16	
28000300	TEMPORARY DITCH CHECKS	EACH	4	4	
28000400	PERIMETER EROSION BARRIER	FOOT	2640	2640	
28100125	STONE RIPRAP, CLASS B3	SQ YD	94	94	
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SO YD	114	114	
35300400	PORTLAND CEMENT CONCRETE BASE COURSE 9"	SQ YD	114	114	
35600716	HOT-MIX ASPHALT BASE COURSE WIDENING, 10"	SO YD	505	505	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.93	0.93	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	220	220	
40600990	TEMPORARY RAMP	SQ YD	100	100	
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	140	140	
44000100	PAVEMENT REMOVAL	SQ YD	425	425	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	65	65	
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1		1
50300225	CONCRETE STRUCTURES	CU YD	0.4		0.4
50300260	BRIDGE DECK GROOVING	SQ YD	399		399
50300300	PROTECTIVE COAT	SO YD	425		425
50400105	PRECAST CONCRETE BRIDGE SLAB	SQ FT	299		299
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SQ FT	2500		2500
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	5340		5340
50800515	BAR SPLICERS	EACH	117		117
* 50901050	STEEL RAILING, TYPE SM	FOOT	232		232
51500100	NAME PLATES	EACH	1		1
54002020	EXPANSION BOLTS 3/4 INCH	EACH	16		16
59000200	EPOXY CRACK INJECTION	FOOT	19		19
* 63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	462.5	462.5	
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4	4	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4	
63200310	GUARDRAIL REMOVAL	FOOT	822	822	

* SPECIALTY ITEM

REVISIONS	
NAME	DATE
K.J.H	1/30/08

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
US 67 OVER TROUBLESOME CREEK
FAP 310 SECTION (39B)I
McDONOUGH COUNTY

SCALE: VERT. DRAWN BY GEW
 HORIZ. DATE #DATE CHECKED BY MJS

TUG PROJ. * 68692000
 PLOT DATE * 1/30/08
 FILE NAME * 011615