

F.A.P. SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
313 1681	HENDERSON	15	4
STA. 625+30.00 TO STA. 625+73.00			
FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT			

SUMMARY OF QUANTITIES

100% STATE SAFETY - 2A
HENDERSON

CODE NO.	ITEM	UNIT	RURAL	TOTAL
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	833	833
70301000	WORKZONE PAVEMENT MARKING REMOVAL	SQ FT	833	833
70400100	TEMPORARY CONCRETE BARRIER	FOOT	325	325
* 78005110	EPOXY PAVEMENT MARKING-LINE 4"	FOOT	572	572
78300100	PAVEMENT MARKING REMOVAL	SQFT	190	190
X0320047	REMOVAL OF EXISTING <i>← PRECAST PRESTRESSED CONCRETE</i> DECK BEAMS	SQFT	386	386
Z0030250	IMPACT ATTENUATORS, TEMPORARY(NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2

* SPECIALTY ITEM

SN.036-0003 US.34
over Old Tom Crk.

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	

SUMMARY OF QUANTITIES

SCALE: VERT. DRAWN BY CEJ
 HORIZ. CHECKED BY
 DATE 12-26-2007

PLOT DATE : 4/26/2007 10:48:47
 FILE NAME : #FILE1681\USER\DRNF\TASTOP\NS\SOUND\4\BRIDGE_Contracts\Ear\geny\PP\Baan\Reports\68771_SN036-88830534overTomCrk.dgn
 PLOT SCALE : #SCALE#
 USER NAME : #BBE#