

F.A.P. R.T.E.	SECTION	COUNTY	TOTAL SHEET SHEETS NO.
639	(123B)I-2	MERCER	15 3
STA. 151+26.40 TO STA. 157+20.66			
FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT			

# SUMMARY OF QUANTITIES

100% STATE SAFETY - 2A  
MERCER

CODE NO.	ITEM	UNIT	RURAL	TOTAL
35600712	HOT MIX ASPHALT BASE COURSE WIDENING, 9"	SQYD	58	58
44000920	BITUMINOUS CONCRETE SHOULDER REMOVAL	SQYD	58	58
50301200	CONCRETE WEARING SURFACE	SQYD	96.2	96.2
50400505	<i>PRECAST PRESTRESSED CONCRETE</i> DECK BEAMS (27" DEPTH)	SQFT	184	184
50400605	<i>PRECAST PRESTRESSED CONCRETE</i> DECK BEAMS (33" DEPTH)	SQFT	448	448
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1650	1650
67100100	MOBILIZATION	LSUM	1	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	LSUM	1	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	LSUM	1	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1

#DATE 08-17-07  
 #FILE #S&L#ENGR#AF#1#STD#PLNS#SD#AD#1#BRIDGE#CONTRACT#E#M#R#P#R#A#B#7#2#S#B#S#R#E#L#1#T#R#E#E#R#D#R#V#R#D#R#  
 #SCALE#  
 #REF#

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

## SUMMARY OF QUANTITIES

SCALE VERT. \_\_\_\_\_  
 HORIZ. \_\_\_\_\_  
 DATE 08-17-2007

DRAWN BY CEJ  
 CHECKED BY \_\_\_\_\_