

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
639	123B11-2	MERCER	15	4
STA. 151+26.40 TO STA. 157+20.66				
FED. ROAD DIST. NO. 4		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

100% STATE SAFETY - 2A
MERCER

CODE NO.	ITEM	UNIT	RURAL	TOTAL
*70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	1404	1404
70301000	WORKZONE PAVEMENT MARKING REMOVAL	SQ FT	1404	1404
70400100	TEMPORARY CONCRETE BARRIER	FOOT	588	588
*78005110	EPOXY PAVEMENT MARKING-LINE 4"	FOOT	1762	1762
78300100	PAVEMENT MARKING REMOVAL	SQFT	529	529
X0301424	SILICONE JOINT SEALER	FOOT	10	10
X0320047	REMOVAL OF EXISTING <i>PRECAST PRESTRESSED CONCRETE</i> DECK BEAMS	SQFT	650	650
X0320887	POLYMER CONCRETE	CUFT	4.2	4.2
X0321781	MECHANICAL SPLICE	EACH	440	440
X5030275	CONCRETE WEARING SURFACE REMOVAL	SQYD	24.1	24.1
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	3	3
Z0030250	IMPACT ATTENUATORS, TEMPORARY(NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2

* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. DATE: 08-18-2007

DRAWN BY CEJ
CHECKED BY