

SUMMARY OF QUANTITIES

CODE NO	PAY ITEM	UNITS	TOTAL QUANTITY	URBAN	100% STATE QUANTITY	90% STATE 10% CITY QUANTITY
					SFTY-2A	Y031-1F
87301525	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 18 6 PAIR	FOOT	303.5			303.5
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	15			15
87502700	TRAFFIC SIGNAL POST, ALUMINUM 16 FT.	EACH	2			2
87702910	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 36 FT.	EACH	1			1
87702920	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 38 FT.	EACH	1			1
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	6			6
87800200	CONCRETE FOUNDATION, TYPE D	FOOT	3.5			3.5
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	22			22
87900200	DRILL EXISTING HANDHOLE	EACH	1			1
* 88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	2			2
88040120	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED	EACH	1			1
88040320	SIGNAL HEAD, POLYCARBONATE, LED, 3-FACE, 1-4 SECTION, 2-5-SECTION, BRACKET MOUNTED	EACH	1			1
88040360	SIGNAL HEAD, POLYCARBONATE, LED, 3-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1			1
88102810	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED	EACH	2			2
88102830	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, BRACKET MOUNTED	EACH	2			2
88200100	TRAFFIC SIGNAL BACKPLATE	EACH	7			7
88800100	PEDESTRIAN PUSH-BUTTON	EACH	6			6
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1			1
89502200	MODIFY EXISTING CONTROLLER	EACH	1			1

* SPECIALTY ITEMS

FILE NAME *	USER NAME *	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ct:\projects\0803508\shstoa.dgn	loughlinr1	DRAWN -	REVISED -			663	17N, TS, I	SANGAMON	25	6	
PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -	REVISED -			CONTRACT NO. 72B75					
PLOT DATE = Feb-21-2008 01:52:39PM	DATE -	REVISED -	REVISED -			SCALE:	SHEET NO. 4 OF 5 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT