

SUMMARY OF QUANTITIES

F&P ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
592	121-1R, 121HVB	ST CLAIR	239	4

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
				1000-2A	X171-5B	Y031-1F			
				80% FEDERAL / 20% IDOT	80% FEDERAL / 20% IDOT	ST. PAUL DR. 80% FED. / 13% IDOT / 7% CAHOKIA	RANGE LANE 80% FED. / 10% IDOT / 10% CAHOKIA	RESURFACING / INNERCONNECT 80% FEDERAL / 20% IDOT	
CODE NO	ITEM	UNIT							
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	242	242					
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	1,630	1,630					
20200100	EARTH EXCAVATION	CU YD	25,655	25,655					
20400800	FURNISHED EXCAVATION	CU YD	159,670	159,670					
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	216		216				
20800150	TRENCH BACKFILL	CU YD	2,047	2,047					
21400100	GRADING AND SHAPING DITCHES	FOOT	120	120					
* 25000100	SEEDING, CLASS 1	ACRE	11.6	11.6					
* 25000305	SEEDING, CLASS 3A	ACRE	4.1	4.1					
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1,413	1,413					
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1,413	1,413					
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1,413	1,413					
* 25000700	AGRICULTURAL GROUND LIMESTONE	TON	31.0	31.0					
* 25100115	MULCH, METHOD 2	ACRE	15.7	15.7					
* 25100630	EROSION CONTROL BLANKET	SQ YD	36,930	36,930					
* 28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	4,710	4,710					
* 28000300	TEMPORARY DITCH CHECKS	EACH	31	31					
* 28000400	PERIMETER EROSION BARRIER	FOOT	3,579	3,579					
28000500	INLET AND PIPE PROTECTION	EACH	23	23					
28100105	STONE RIPRAP, CLASS A3	SQ YD	21	21					
30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	33,676	33,676					
30201500	LIME	TON	673.0	673.0					
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	14,794	14,794					
31102000	SUB-BASE GRANULAR MATERIAL, TYPE C	CU YD	118	118					
35100500	AGGREGATE BASE COURSE, TYPE A 6"	SQ YD	712	712					
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	107	107					
35600708	HOT-MIX ASPHALT BASE COURSE WIDENING, 8"	SQ YD	35	35					
40200500	AGGREGATE SURFACE COURSE, TYPE A 6"	SQ YD	81	81					
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	1,000	1,000					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	19.6	19.6					
40600300	AGGREGATE (PRIME COAT)	TON	116	116					
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	165	165					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	163	163					
40603090	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	2,109	2,109					
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	3,999	3,999					
40701821	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 7"	SQ YD	3,168	3,168					
40701851	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 8 1/2"	SQ YD	2,273	2,273					
40701871	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 9 1/2"	SQ YD	6,879	6,879					
40701966	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 14 1/4"	SQ YD	25,560	25,560					

* SPECIALTY ITEM

Rev.