

# SUMMARY OF QUANTITIES

FAP ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
592	121-1R, 121HV	ST CLAIR	239	8

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		I000-2A	X171-5B	Y031-1F		
				80% FEDERAL / 20% IDOT	80% FEDERAL / 20% IDOT	ST. PAUL DR. 80% FED. / 13% IDOT / 7% CAHOKIA	RANGE LANE 80% FED. / 10% IDOT / 10% CAHOKIA	RESURFACING / INNERCONNECT 80% FEDERAL / 20% IDOT
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2				
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	53	53				
66700095	PERMANENT SURVEY MARKERS	EACH	7	7				
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	59	59				
* 66900400	SPECIAL WASTE GROUND WATER DISPOSAL	GALLON	20,000	20,000				
* 66900450	SPECIAL WASTE PLANS AND REPORT	L SUM	1	1				
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	2	2				
* 66901000	BACKFILL PLUGS	CU YD	30	30				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	24	24				
67000600	ENGINEER'S FIELD LABORATORY	CAL MO	24	24				
67100100	MOBILIZATION	L SUM	1	1				
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1				
70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	L SUM	1	1				
70100400	TRAFFIC CONTROL AND PROTECTION, STANDARD 701431	EACH	4	4				
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1	1				
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1				
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	19,700	19,700				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	350	350				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	63,500	63,500				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2,546	2,546				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	5,100	5,100				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	160	160				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	22,500	22,500				
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1,603	1,603				
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	943	943				
* 72000100	SIGN PANEL - TYPE 1	SQ FT	173	173				
* 72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	9	9				
* 72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	27	27				
* 73000100	WOOD SIGN SUPPORT	FOOT	208	208				
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	804	804				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	49,979	49,979				
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	260	260				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2,649	2,649				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	817	817				
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	1,020	1,020				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	656	656				
* 78100200	TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER	EACH	340	340				
* 78200300	PRISMATIC CURB REFLECTOR	EACH	169	169				

\* SPECIALTY ITEM