

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1832	5BR-2	CALHOUN	68	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

TREE REMOVAL SCHEDULE

STATION	OFFSET	RT/LT	6 TO 15 UNITS					OVER 15 UNITS							
465+23.24	22.3	LT										38			
465+43.75	43.6	RT				15									
465+48.14	23.6	LT										38			
465+58.37	41.2	RT				15									
465+85.23	26.5	LT									36				
466+42.07	49.0	RT		12											
466+56.60	46.2	RT											48		
466+79.85	40.6	RT											48		
467+03.00	45.3	RT												60	
467+04.57	39.3	LT											48		
467+20.40	43.1	RT										40			
467+21.94	37.4	RT						30							
468+02.03	28.4	LT											48		
468+77.21	44.4	RT											48		
469+21.33	41.5	RT						24							
469+27.01	42.1	RT						24							
469+36.35	46.2	RT							30						
469+44.92	46.2	RT		12											
469+60.89	45.0	RT		10											
469+64.99	45.3	RT						24							
469+70.25	44.6	RT						24							
469+77.47	44.4	RT							30						
469+86.29	44.3	RT								32					
469+94.04	46.2	RT				15									
470+04.75	43.0	RT					24								
470+08.14	43.3	RT						30							
470+13.43	42.6	RT					20								
470+20.74	43.1	RT					20								
470+26.27	42.8	RT	8												
470+75.46	40.3	RT					20								
470+79.62	40.9	RT				12									
470+94.52	42.7	RT										40			
SUB-TOTAL			8	10	36	45	60	120	120	32	36	76	80	240	60
TOTAL			99			824									

EARTHWORK SCHEDULE

LOCATION	EARTH EXCAVATION (CU YD)	EARTH EXCAVATION ADJTD FOR SHRINKAGE (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
STA. 469+50.00 TO STA. 471+15.00	196.8	147.6	0.0	147.6
TOTAL	196.6	147.6	0.0	147.6

EARTHWORK SCHEDULE (WIDENING)

LOCATION	EARTH EXCAVATION (CU YD)	EARTH EXCAVATION ADJTD FOR SHRINKAGE (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
STA. 463+70.00 TO STA. 466+71.50	37.7	28.3	0.0	28.3
STA. 468+11.50 TO STA. 471+21.00	38.7	29.0	0.0	29.0
TOTAL	76.4	57.3	0.0	57.3

REMOVAL SCHEDULE

LOCATION					PVMT REMOVAL		HMA SURF REMOVAL VAR. DEPTH (SQ YD)	SPBGR (FT)
FROM	OFFSET	TO	OFFSET	RT/LT	MAINLINE REMOVAL (SQ YD)	WIDENING REMOVAL (SQ YD)		
463+70.00		466+71.50		LT		150.75		
463+71.25		466+71.75		LT			300.50	
464+15.00		465+04.86		RT/LT			239.63	
465+02.25		467+04.25		RT			202.00	
466+71.39		467+18.86		RT/LT	146.00			
467+91.45		468+47.42		RT/LT	168.02			
468+10.50		471+11.00		LT		154.75	300.50	
468+11.50		471+21.00		LT				
468+30.50		469+96.00		RT			165.50	
470+11.81		471+15.00		RT/LT			275.17	
471+44.97		SIDE ROAD		LT			89.79	
TOTAL					314.02	305.50	604.59	968.50
					619.52			

RIGHT-OF-WAY MARKERS SCHEDULE

LOCATION			ROW MARKERS (EA)
STATION	RT/LT	OFFSET	
458+69.65	RT	128.72	1
458+70.43	RT	28.72	1
459+50.00	RT	POC	1
460+16.75	RT	129.77	1
460+17.34	LT	45.23	1
462+86.09	LT	45.39	1
462+91.47	RT	129.53	1
463+66.65	LT	67.24	1
465+50.00	RT	POC	1
467+00.00	LT	POC	1
467+92.64	RT	87.06	1
468+12.17	RT	127.14	1
469+50.00	RT	POC	1
470+83.62	LT	65.79	1
470+92.63	RT	89.32	1
471+07.27	LT	95.87	1
TOTAL			16

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 FAP ROUTE 304
 SECTION 5BR-2
 CALHOUN COUNTY

SCALE: VERT. _____
 HORIZ. _____
 DATE _____

DRAWN BY _____
 CHECKED BY _____

PLOT DATE = 1/30/2008
 FILE NAME = c:\pms\jesta\ad\9805\plan\091005.dgn
 PLOTTER = HP DesignJet 500 / JPL
 REFERENCE = REF#