

EARTHWORK SCHEDULE - IL158									
LOCATION				EARTH EXCAVATION	EMBANKMENT REQUIRED	EARTH EXCAVATION AVAILABLE (25% SHRINKAGE)	FURNISHED EXCAVATION	LIME	PROCESSING MODIFIED SOIL 12"
STATION	TO	STATION	* LT/RT	CU YD	CU YD	CU YD	CU YD	TON	SQ YD
IL 158 @ WHERRY ROAD									
198+40 NB	TO	204+60 NB	RT	246.0	22.0	184.5	-162.5	18.0	936.3
PROFILE CORRECTIONS - IL 158									
288+20 NB	TO	297+26 NB	LT		201.3		201.3		
288+20 NB	TO	297+26 NB	RT		423.5		423.5		
289+10 SB	TO	297+33 SB	LT		744.7		744.7		
289+10 SB	TO	297+33 SB	RT		440.0		440.0		
BRIDGE OMISSION									
299+95 SB	TO	307+00 SB	LT		139.7		139.7		
299+95 SB	TO	307+00 SB	RT		119.9		119.9		
300+14 NB	TO	306+75 NB	LT		143.0		143.0		
300+14 NB	TO	306+75 NB	RT		86.9		86.9		
TOTALS				246.0	2,321.0	184.5	2,136.5	18.0	936.3
TOTALS (ROUNDED FOR SUMMARY)				246			2,137	19	937

* ORIENTATION LOOKING UP STATION

FILE NAME = C3-9.SCHEDULES_IL158.dgn	USER NAME = awoiz	DESIGNED - DHP	REVISED - 03/12/08	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	EARTHWORK SCHEDULE - IL 158 & SIDE ROADS	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		DRAWN - EDW	REVISED -			674	410, 410-1-1	ST. CLAIR	41	4	
		CHECKED - SAR	REVISED -			CONTRACT NO. 76B14					
		DATE - 01/30/08	REVISED -			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					
				SCALE:	SHEET NO. OF SHEETS	STA.	TO STA.				