



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 4, 2008

SUBJECT: FAI Route 270  
Project ACHSIP-270-5 (082) 001  
Section 60-(1,2,3,4,5)I  
Madison County  
Contract No. 76B17  
Item No. 176, April 25, 2008 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page i of the Table of Contents to the Special Provisions.
2. Revised page 4 of the Special Provisions.
3. Added page 39 to the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Eric E. Harm  
Interim Bureau Chief  
Bureau of Design and Environment

A handwritten signature in black ink, appearing to read 'Ted B. Walschleger P.E.'.

By: Ted B. Walschleger, P. E.  
Engineer of Project Management

cc: Mary C. Lamie, Region 5, District 8; Roger Driskell; Estimates

TBW:DB:jc

**TABLE OF CONTENTS**

LOCATION OF PROJECT ..... 1

DESCRIPTION OF PROJECT ..... 1

MONTHLY LABOR SUMMARY AND ACTIVITY REPORTING SYSTEM ..... 1

SEEDING CLASS 2 OR 2A ..... 4

TRAFFIC CONTROL PLAN ..... 4

STATUS OF UTILITIES TO BE ADJUSTED ..... 5

COOPERATION BETWEEN CONTRACTORS..... 5

WORK ZONE LANE RESTRICTIONS..... 6

FAILURE TO OPEN TRAFFIC LANES TO TRAFFIC FOR PEAK PERIODS..... 6

IMPACT ATTENUATOR REMOVAL ..... 6

REMOVE TEMPORARY CONCRETE BARRIER ..... 7

DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE) ..... 7

EQUIPMENT RENTAL RATES (BDE)..... 14

EROSION AND SEDIMENT CONTROL DEFICIENCY DEDUCTION (BDE) ..... 15

HIGH TENSION CABLE MEDIAN BARRIER (BDE) ..... 16

PAYMENTS TO SUBCONTRACTORS (BDE) ..... 18

RECLAIMED ASPHALT PAVEMENT (RAP) (BDE) ..... 19

REFLECTIVE SHEETING ON CHANNELIZING DEVICES (BDE) ..... 24

SEEDING (BDE) ..... 25

SILT FILTER FENCE (BDE) ..... 26

SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) ..... 27

TEMPORARY EROSION CONTROL (BDE) ..... 27

TRAINING SPECIAL PROVISIONS ..... 28

LIGHTING FOR NIGHTTIME HIGHWAY CONSTRUCTION ..... 30

COMPLETION DATE (VIA CALENDAR DAYS) (BDE) ..... 32

HOT-MIX ASPHALT - FIELD VOIDS IN THE MINERAL AGGREGATE (BDE) ..... 32

HOT-MIX ASPHALT – PLANT TEST FREQUENCY (BDE) ..... 34

HOT-MIX ASPHALT – TRANSPORTATION (BDE) ..... 36

BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE) (RETURN FORM WITH BID) ..... 36

RESTRICTIONS ON PROPOSED LANE CLOSURES ..... 39

Revised 04/04/2008

**SEEDING CLASS 2 OR 2A**

*Effective: February 5, 1975*

*Revised: February 6, 2007*

All disturbed areas are to be seeded.

The seed mixtures shall be modified as follows:

Seeding Class 2 – Inferno Tall Fescue or Tarheel II Tall Fescue shall be replaced with Alta Fescue or KY31 at 100 lb/acre (110 kg/ha).

Seeding Class 2A – Inferno Tall Fescue or Tarheel II Tall Fescue shall be replaced with Alta Fescue or KY31 at 60 lb/acre (70 kg/ha). Dawsons Red may be substituted for Audobon Red Fescue at 30 lb/acre (35 kg/ha).

When Class 2 seeding is done between March 1<sup>st</sup> and June 1st, the seed mixture shall also include 48 pounds per acre (55kg/ha) of Spring Oats.

When Class 2 seeding is done between August 1st and November 15th, the seed mixture shall also include 56 pounds per acre (63kg/ha) of Balboa Farm Rye or 60 pounds per acre (67kg/ha) of Winter Wheat.

This work will be paid for at the contract unit price per acre (hectare) for SEEDING CLASS 2 or SEEDING CLASS 2A.

The amount of Seeding Class 2 or 2A shown in the contract has been estimated. The Contractor will be paid for the amount actually seeded, at the contract unit price bid per acre (hectare), as directed by the Engineer.

**TRAFFIC CONTROL PLAN**

*Effective: July 12, 1993*

*Revised: May 12, 1997*

Traffic control shall be in accordance with the applicable sections of the “Standard Specifications for Road and Bridge Construction”, the applicable guidelines contained in the “National Manual on Uniform Traffic Control Devices for Streets and Highways”, Illinois Supplement to the National Manual of Uniform Traffic Control Devices, these Special Provisions, and any special details and Highway Standards contained herein and in the plans.

Special attention is called to Articles 107.09 and 107.14 of the “Standard Specifications for Road and Bridge Construction and the following Highway Standards relating to traffic control:

701101      701400      **701401**      701426      701901

In addition, the following Special Provision(s) will also govern traffic control for this project:

- Cooperation Between Contactors
- Work Zone Lane Restrictions
- Failure to Open Traffic Lanes to Traffic for Peak Periods

Revised 04/04/2008

## **RESTRICTIONS ON PROPOSED LANE CLOSURES**

The Contractor shall verify with the Engineer the precise location of each proposed lane closure twenty-four (24) hours prior to possibly closing the lane. The location of the lane closure shall become subject to the approval of the Engineer with respect to the other active contracts working in the vicinity. The Engineer shall coordinate the lane closure such that the cooperation of the contractors minimizes the disruption to the traveling public. If the said notice is not provided, lane closures will not be permitted.

No additional compensation will be allowed for this coordination.

Added 04/04/2008