

SUMMARY OF QUANTITIES

CODE NO	ITEM	CONSTRUCTION TYPE CODE		J000
		UNIT	ROADWAY STATE	100%
20200100	EARTH EXCAVATION	CU YD		175
25100630	EROSION CONTROL BLANKET	SQ YD		270
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD		390
35300400	PORTLAND CEMENT CONCRETE BASE COURSE 9"	SQ YD		263
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON		132
40600300	AGGREGATE (PRIME COAT)	TON		3
40600990	TEMPORARY RAMP	SQ YD		114
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON		70
40603320	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N90	TON		132
42001300	PROTECTIVE COAT	SQ YD		88
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT		977
42400800	DETECTABLE WARNINGS	SQ FT		77
44000100	PAVEMENT REMOVAL	SQ YD		61
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD		1214
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD		5
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT		235
44000600	SIDEWALK REMOVAL	SQ FT		1072
44201361	CLASS C PATCHES, TYPE I, 11 INCH	SQ YD		19
44201365	CLASS C PATCHES, TYPE II, 11 INCH	SQ YD		15
44201369	CLASS C PATCHES, TYPE III, 11 INCH	SQ YD		68
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD		11
50300255	CONCRETE STRUCTURES	CU YD		1.9
50800105	REINFORCEMENT BARS	POUND		122
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT		318
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO		3
67100100	MOBILIZATION	L SUM		1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM		1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM		1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT		1272
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT		339
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT		369
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT		64
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT		850
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT		339
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT		369
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT		64

* SPECIALTY ITEMS