F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2744	06-00183-00-CH	COOK	73	7
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 83999

SUMMARY OF QUANTITIES

	IDOT CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	CONSTRUCTION TYPE CODES							
					I000-1A ROADWAY 80% IDOT 20% WILMETTE	Y030-1E LIGHTING 80% IDOT 20% WILMETTE	Y031-1F TRAFFIC SIGNALS LAKE AVE 80% IDOT 20%WILMETTE	CENTRAL AVE 80% IDOT 20% WILMETTE	WILMETTE AVE 80% IDOT 20% WILMETTE	LINDEN AVE 80% IDOT 20% WILMETTE	INTERCONNECT 80% IDOT 20% WILMETTE	VILLAGE OF WILMETTE 100% WILMETTE
Δ	89100400	ILLUMINATED SIGN, LED	EACH	10			2	2	2	4		
Δ	89501300	RELOCATE EXISTING MAST ARM ASSEMBLY AND POLE	EACH	1					1			
Δ	89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	21830			9861	5484	6485			
Δ	89502350	REMOVE AND REINSTALL ELECTRIC CABLE IN CONDUIT	FOOT	93			93					
Δ	89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	4			1	1	1	1		
Δ	89502380	REMOVE EXISTING HANDHOLE	EACH	7			6	1				
Δ	89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	10			5	2	3			
	X0322102	TEMPORARY SIDEWALK RAMP	EACH	10	10							
*	X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	96	96							
*	X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	51	51							
Δ	X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	6		6						
Δ	X0324007	OPTIMIZE TRAFFIC SIGNAL SYSTEM	EACH	1							1	
Δ	X0325737	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	4			1	1	1	1		
	X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	2	2							
	X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	7	7							
Δ	X8161000	EXPOSE AND RELOCATE EXISTING UNIT DUCT	FOOT	50		50						
Δ	X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1 /C	FOOT	322			322					
Δ	X8730250	ELECTRIC CABLE IN CONDUIT, NO. 20 3/C, TWISTED, SHIELDED	FOOT	2129								2129
Δ	X8950200	REBUILD EXISTING HANDHOLE	EACH	7			3	4				
Δ	X8950205	REBUILD EXISTING HANDHOLE, SPECIAL	EACH	1			1					
Δ	XX002094	REMOVE AND REINSTALL FIBER OPTIC CABLE IN CONDUIT	LSUM	1							1	
Δ	XX002185	RELOCATE EXISTING LIGHT POLE	EACH	6		6						
Δ	XX002264	ELECTRIC CABLE IN CONDUIT, RAILROAD, NO.14-3C	FOOT	232			232					
Δ	XX006495	LIGHT POLE FOUNDATION, 18-INCH DIAMETER	FOOT	22		22						
*	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1							
*	Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1							
*	Z0036900	PARKING METER TO BE REMOVED	EACH	1	1							
+	Z0076600	TRAINEES	HOUR	500	500							
*	XX007279	CONCRETE ACCENT PAVER REMOVE AND STORE	SQ FT	1486	1486							
*	XX007280	CONCRETE ACCENT PAVER RE-INSTALLATION	SQ FT	1159	1159							
Δ	XX007281	UNIT DUCT, 600V, 2-1/C No. 2, 2-1/C NO. 4, 1/C NO. 2 GROUND (XLP TYPE USE), 1-1/2 INCH DIAMETER POLYETHYLENE	FOOT	164		164						

+ Y080
Δ SPECIALTY ITEMS

PLAN — SURVEYED / PLOTTED / ALIGNMENT CHECKED / RIGHT-OF-WAY CHECKED / CADD FILE NAME / NOTE BOOK NO. / BY / DATE

PROFILE — SURVEYED / PLOTTED / GRADES CHECKED / STRUCTURE NOTATIONS CHKD / NOTE BOOK NO. / BY / DATE

REVISIONS	
NAME	DATE

SUMMARY OF QUANTITIES

SHEET 4 OF 4

CONSULTANT
TYLIN INTERNATIONAL

VILLAGE OF WILMETTE
GREEN BAY ROAD
INTERSECTION IMPROVEMENTS

DRAWN: CBS
CHECKED:
APPROVED:
DATE: 02-14-2008
SCALE: NONE
JOB NO.:
SHEET NO.
PROJECT NO.: