

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6761	04-00057-06-WR	TAZEWELL	154	6
STA.		TO STA.		
FED. ROAD DIST. NO. 4		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES				TAZEWELL COUNTY 80% FEDERAL / 20% STATE CONSTRUCTION TYPE CODE	
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	1000 - 2A	2020 - 2A
542D0235	PIPE CULVERTS, CLASS D, TYPE 1 30"	FOOT	32	32	
542D0241	PIPE CULVERTS, CLASS D, TYPE 1 36"	FOOT	32	32	
542D1060	PIPE CULVERTS, CLASS D, TYPE 2 15"	FOOT	75	75	
54213450	END SECTIONS 15"	EACH	12	12	
54213453	END SECTIONS 18"	EACH	22	22	
54213459	END SECTIONS 24"	EACH	1	1	
54213465	END SECTIONS 30"	EACH	2	2	
54213471	END SECTIONS 36"	EACH	1	1	
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	2	2	
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	8	8	
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	6	6	
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	2	2	
54248510	CONCRETE COLLAR	CU YD	0.9	0.9	
550A0070	STORM SEWER CLASS A, TYPE 1, 15"	FOOT	46	46	
550A0090	STORM SEWER CLASS A, TYPE 1, 18"	FOOT	518	518	
550A0360	STORM SEWER CLASS A, TYPE 2, 15"	FOOT	201	201	
550A0380	STORM SEWER CLASS A, TYPE 2, 18"	FOOT	160	160	
550A0450	STORM SEWER CLASS A, TYPE 2, 36"	FOOT	106	106	
60100955	PIPE DRAINS 15"	FOOT	194	194	
60218300	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1	
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	6	6	
60221000	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	2	2	
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	5	5	
60234200	INLETS TYPE A, TYPE 1 FRAME, OPEN LID	EACH	2	2	
60240210	INLETS, TYPE B, TYPE 1, FRAME OPEN LID	EACH	1	1	
60240301	INLETS, TYPE B, TY 8 GRATE	EACH	3	3	
60241900	INLETS, TYPE G-1, SPECIAL	EACH	5	5	
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	25	25	
60600097	CLASS SI CONCRETE (OUTLET), SPECIAL	CU YD	13.5	13.5	
60603400	GUTTER OUTLET (SPECIAL)	EACH	5	5	
60603600	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	184	184	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	2,649	2,649	
60611610	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-MODIFIED	FOOT	2,370	2,370	
* 63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	1,525	1,525	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)	EACH	8	8	
63200310	GUARDRAIL REMOVAL	FOOT	13	13	
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	63	63	
66700095	PERMANENT SURVEY MARKERS	EACH	5	5	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	9	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**BROADWAY ROAD IMPROVEMENTS  
SUMMARY OF QUANTITIES**

SCALE: AS SHOWN  
DATE 12/07/2007

DRAWN BY DLC  
CHECKED BY REW