

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6761	04-00057-06-WR	TAZEWELL	154	19
STA.		TO STA.		
FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT				

CULVERT SCHEDULE (CONTINUED)				END SECTIONS 18"	END SECTIONS 18"	END SECTIONS 24"	END SECTIONS 30"	END SECTIONS 36"	PRECAST REINFORCED CONCRETE FLARED END SECTION, 15"	PRECAST REINFORCED CONCRETE FLARED END SECTION, 18"	PRECAST REINFORCED CONCRETE FLARED END SECTION, 24"	PRECAST REINFORCED CONCRETE FLARED END SECTION, 36"	PIPE CULVERTS, CLASS A, TYPE 1 15"	PIPE CULVERTS, CLASS A, TYPE 1 18"	PIPE CULVERTS, CLASS A, TYPE 1 24"	PIPE CULVERTS, CLASS A, TYPE 2 24"	PIPE CULVERTS, CLASS A, TYPE 2 36"	PIPE CULVERTS, CLASS A, TYPE 3 36"	PIPE CULVERTS, CLASS D, TYPE 1 15"	PIPE CULVERTS, CLASS D, TYPE 1 18"	PIPE CULVERTS, CLASS D, TYPE 1 24"	PIPE CULVERTS, CLASS D, TYPE 1 30"	PIPE CULVERTS, CLASS D, TYPE 1 36"	PIPE CULVERTS, CLASS D, TYPE 2 15"	PIPE DRAINS 15"		
LOCATION				EA	EA		EA	EA	EA	EA	EA	EA	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	
STA. 53+84.70			RT										1														
STA. 53+84.70	TO	STA. 54+17.80	RT																								
STA. 56+81.50	TO	STA. 58+05.00	RT																								
STA. 56+85.00			RT																								
STA. 57+81.80	TO	STA. 57+85.00	LT																								
STA. 57+85.00			LT																								
STA. 58+10.60	TO	STA. 59+00.00	LT																								
STA. 58+10.60			LT																								
STA. 58+36.00	TO	STA. 59+73.00	RT																								
STA. 59+73.40	TO	STA. 59+78.30	RT																								
STA. 59+73.40	TO	STA. 60+47.00	RT																								
STA. 59+78.30			RT																								
STA. 68+22.00			LT																								
STA. 70+25.00			RT																								
STA. 70+25.00	TO	STA. 70+84.70	RT																								
STA. 70+84.70			RT																								
STA. 71+30.00	TO	STA. 72+07.80	LT																								
STA. 74+10.00			RT																								
STA. 74+10.00	TO	STA. 75+61.00	RT																								
STA. 57+77.80			RT																								
STA. 57+77.80	TO	STA. 57+81.30	RT																								
STA. 67+71.80	TO	STA. 67+70.10	RT																								
STA. 67+70.10			RT																								
STA. 68+17.00	TO	STA. 68+22.00	LT																								
STA. 71+30.00			LT																								
STA. 72+07.80			LT																								
STA. 68+19.00	TO	STA. 68+17.00	LT																								
TOTAL				12	22	1	2	1	2	8	6	2	90	375	121	69	132	64	81	1106	15	32	32	75	194		

PLOT DATE = 2/11/2008
 PLOT SCALE = 2.0000 / IN.
 USER NAME = IDOT

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
BROADWAY ROAD IMPROVEMENTS
SCHEDULE OF QUANTITIES

DATE 12/07/2007

DRAWN BY DLC
 CHECKED BY REW