

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6761	04-00057-06-WR	TAZEWELL	154	20
STA.		TO STA.		
FED. ROAD DIST. NO. 4		ILLINOIS FED. AID PROJECT		

DRAINAGE SCHEDULE

LOCATION	STORM SEWER, CLASS A, TY 1 15"	STORM SEWER, TYPE 1, WATER MAIN QUALITY PIPE, 15"	STORM SEWER, CLASS A, TY 1 18"	STORM SEWER, CLASS A, TY 2 15"	STORM SEWER, CLASS A, TY 2 18"	STORM SEWER, CLASS A TY 2 36"	MANHOLES, TYPE A, 4'-DIAMETER, TY 1 FRAME AND OPEN LID	MANHOLES, TYPE A, 4'-DIAMETER, TY 1 FRAME AND CLOSED LID	MANHOLES, TYPE A, 5'-DIAMETER, TY 1 FRAME AND CLOSED LID	MANHOLES, TYPE A, 5'-DIAMETER, TY 1 FRAME AND OPEN LID	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	INLETS, TYPE B, TYPE 1 FRAME, OPEN LID	INLETS, TYPE B, TY 8 GRATE	INLETS, TYPE B, TY 8 GRATE WITH FLAT SLAB TOP	INLETS, TYPE G-1, SPECIAL	INLETS, TYPE G-1, SPECIAL, DOUBLE	VANE GRATES FOR TYPE G-1 INLETS		INLET MANHOLE, TY G-1, 4' DIA, SPECIAL	TRENCH BACKFILL	
																	LEFT FLOW	RIGHT FLOW			
FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	CU YD
STA. 8+79.00 TO STA. 8+88.00	LT	10																			4.6
STA. 8+89.10	LT															1					
STA. 10+75.00	LT																		1		
STA. 8+89.10 TO STA. 10+75.00	LT		182																		94.4
STA. 10+75.00	LT	6																			2.8
STA. 10+75.00	LT										1										
STA. 10+75.00	RT														1						
STA. 10+75.00 TO STA. 12+00.00	LT			122																	72.3
STA. 10+75.00 TO STA. 11+05.00	RT	30																			4.6
STA. 12+00.00	LT																			1	1
STA. 12+00.00 TO STA. 12+94.23	LT					90															5.2
STA. 12+94.23	LT									1											
STA. 12+94.23 TO STA. 13+67.61	LT					70															
STA. 13+60.53 TO STA. 13+67.61	LT															1		1	1		
STA. 13+67.61	LT				18																3.7
STA. 13+60.53 TO STA. 13+67.61	RT									1						1		1	1		
STA. 13+67.61	CL		40																		20.7
STA. 15+00.00	LT															1		1			3.7
STA. 24+45.00	RT								1												18.5
STA. 25+49.29	LT															1					18.2
STA. 30+27.80	RT																				48.7
STA. 36+00.00	LT													1							
STA. 38+00.00	LT													1							
STA. 39+00.00	LT									1											
STA. 42+21.00	LT															1		1			4.8
STA. 46+05.00 TO STA. 46+88.00	LT			82																	
STA. 46+88.00	LT																		1		51.9
STA. 46+88.00 TO STA. 48+00.00	LT			109																	15.8
STA. 48+00.00	LT																			1	
STA. 48+00.00 TO STA. 50+08.80	LT			205																	21.8
STA. 50+08.80	LT																				47.7
STA. 54+17.80	RT								1												
STA. 54+84.00	LT																				
STA. 56+61.50	RT																				
STA. 57+61.60	LT									1											
STA. 57+81.30	RT																				
STA. 58+38.40	RT																				
STA. 58+10.60 TO STA. 59+00.00	LT					106															
STA. 59+00.00	LT																				
STA. 59+00.00 TO STA. 60+25.00	LT				126																
STA. 59+73.40	RT									1											
STA. 67+12.00 TO STA. 67+71.80	RT				57																
STA. 67+71.80	RT																				
STA. 68+17.00	LT																				
TOTAL		48	222	518	291	160	106	1	6	5	2	2	1	3	5	2	5	5	3		437

PLOT DATE = 2/11/2008
 PLOT SCALE = 2.0000
 USER NAME = IDOT

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
BROADWAY ROAD IMPROVEMENTS
SCHEDULE OF QUANTITIES
 DATE 12/07/2007
 DRAWN BY DLC
 CHECKED BY REW