



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 2, 2008

SUBJECT: TR 23 (Newburg Road)
Project BROS-115(64)
Section 05-04163-00-BR
Macon County
Contract No. 95543
Item 69
April 25, 2008 Letting
Addendum (A)

TO PROSPECTIVE BIDDERS:

Due to clarify information necessary to revise the following:

Plans – Sheets 1, 2, 5, & 6.

Proposal – Page 2 of the Schedule of Prices, page 3 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Eric Harm
Interim Engineer of Design and Environment

A handwritten signature in black ink, appearing to read 'Ted B. Walschleger', followed by the letters 'A.E.' in a smaller font.

By: Ted B. Walschleger
Engineer of Project Development
and Implementation

TR 23
05-04163-00-BR
MACON

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF PRICES
CONTRACT NUMBER - 95543

ECMS002 DTGECM03 ECMR003 PAGE 2
RUN DATE - 04/02/08
RUN TIME - 072419

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
50900205	STEEL RAILING TY S1	FOOT	300.000 X	=			
51201105	FUR MET SHELL PILE 14	FOOT	585.000 X	=			
51202305	DRIVING PILES	FOOT	585.000 X	=			
51203200	TEST PILE MET SHELLS	EACH	2.000 X	=			
51500100	NAME PLATES	EACH	1.000 X	=			
59300100	CONTR LOW-STRENG MATL	CU YD	48.000 X	=			
66500105	WOV W FENCE 4	FOOT	409.000 X	=			
66502300	WOV W FENCE REMOV	FOOT	408.000 X	=			
67100100	MOBILIZATION	L SUM	1.000 X	=			
70101830	TRAF CONT-PROT BLR 21	L SUM	1.000 X	=			
72000100	SIGN PANEL T1	SQ FT	10.000 X	=			
72500100	OBJECT MARKER T1	EACH	2.000 X	=			
72900100	METAL POST TY A	FOOT	44.000 X	=			
78201000	TERMINAL MARKER - DA	EACH	4.000 X	=			

TOTAL \$

REVISED 4-2-08

NOTE:
*** PLEASE TURN PAGE FOR IMPORTANT NOTES ***

For the purpose of this contract, no seeding will be permitted when the ground is frozen, wet or in any otherwise untillable condition.

Between November 1st and December 31st, the Contractor shall substitute 4 lb of Perennial Ryegrass for the 48 lb of Oats, Spring.

Erosion Control Blanket shall be placed on the seeded areas in accordance with Article 251.04.

Revise Articles 250.10 and 251.07 so that the following applies:

Basis of Payment: This work shall be paid for at the contract unit price per acre for SEEDING, CLASS 2 (SPECIAL). The items of Erosion Control Blanket and Fertilizer Nutrients will not be paid for separately but shall be considered as included to the contract unit price per acre for SEEDING CLASS 2 (SPECIAL).

TRAFFIC CONTROL PLAN

TR 23 (Dantown Road) shall be closed to traffic.

Traffic control shall be in accordance with the applicable sections of the Standard Specifications for Road and Bridge Construction, the applicable guidelines contained in the Illinois Manual of Uniform Traffic Control Devices for Streets and Highways, these Special Provisions, and any special details and Highway Standards contained herein and in the plans.

Special attention is called to Article 107.09 and 107.14 of the Standard Specifications for Road and Bridge Construction, the Highway Standards, and other special provisions relating to traffic control.

Traffic control and protection will be provided in accordance with the following standards:

Standard BLR 21
Standard 701901

In addition to the barricades required for the above, two sets of staggered barricades with "ROAD CLOSED TO THROUGH TRAFFIC" signs will be required and placed as directed by the Engineer, near the intersection of Cemetery Road and Dantown Road.

This work shall be paid for at the contract unit price lump sum for TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21, which includes all labor, material, and equipment necessary to perform the work for the duration of the project.