

**CURB AND GUTTER REMOVAL
AND REPLACEMENT SCHEDULE**

| STATION | LIN. FT. | STATION | LIN. FT. |
|--------------------|----------|--------------------|----------|
| 0+79 RT TO 0+95 RT | 16 | 4+27 RT TO 4+45 RT | 19 |
| 1+24 LT TO 1+39 LT | 26 | 4+80 LT TO 4+92 LT | 24 |
| 1+25 RT TO 1+28 RT | 8 | 4+80 RT TO 5+20 RT | 40 |
| 2+19 RT TO 2+76 RT | 67 | 5+74 RT TO 5+95 RT | 21 |
| 2+75 LT | 10 | 6+30 RT TO 6+40 RT | 10 |
| 2+94 RT TO 3+03 RT | 12 | 6+60 LT TO 6+75 LT | 15 |
| 3+10 RT TO 3+15 RT | 5 | 7+08 RT TO 7+18 RT | 10 |
| 3+34 RT TO 3+49 RT | 15 | 7+16 LT TO 7+54 LT | 38 |
| 3+77 RT TO 3+85 RT | 8 | 7+67 LT TO 8+33 LT | 66 |
| 4+13 LT TO 4+35 LT | 22 | 8+31 RT TO 8+38 RT | 7 |

TOTAL 439

| ROUTE | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|----------------|----------------|-------------|--------------|-----------|
| | 06-00054-00-SW | FRANKLIN | 8 | 2 |
| WEST FRANKFORT | | MAIN STREET | | |

**CONTRACT NO. 99302
PROJECT NO. TE-00D9(93)**

SUMMARY OF QUANTITIES

| ITEM NO. | PAY ITEM | UNIT | QUANTITY |
|-------------|---|---------|----------------|
| | | | <i>SFTY-1B</i> |
| 42400100 | PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH | SQ. FT. | 370 |
| 42400600• | PORTLAND CEMENT CONCRETE SIDEWALK SPECIAL | SQ. FT. | 15,890 |
| 42400800 | DETECTABLE WARNINGS | SQ. FT. | 114 |
| 44000600• | SIDEWALK REMOVAL | SQ. FT. | 16,260 |
| 44001700• | COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT | FOOT | 439 |
| 67100100 | MOBILIZATION | L SUM | 1 |
| △ A2008016 | TREE, TILIA CORDATA (LITTLE LEAF LINDEN) 2' CALIPER, BALLED AND BURLAPPED | EACH | 8 |
| △ X0300635• | PLANTER | EACH | 4 |
| △ X0444100• | BENCHES | EACH | 4 |
| △ XX002918• | TREE FRAME AND GRATES | EACH | 8 |
| △ Z0020000• | ELECTRICAL SYSTEM COMPLETE | L SUM | 1 |

△ SPECIALTY ITEMS

**TREE, FRAME
AND GRATE
LOCATIONS**

| STATION | OFFSET |
|---------|--------|
| 1+99 | 31' RT |
| 2+38 | 31' LT |
| 3+68 | 31' RT |
| 3+86 | 31' LT |
| 5+30 | 31' RT |
| 5+88 | 31' LT |
| 7+26 | 31' LT |
| 7+85 | 31' RT |

SIDEWALK REMOVAL AND REPLACEMENT SCHEDULE

| STATION | SIDEWALK REMOVAL SQ. FT. | PC SIDEWALK SQ. FT. | PC SW SPECIAL SQ. FT. | DETECTABLE WARNINGS SQ. FT. |
|--------------------|--------------------------|---------------------|-----------------------|-----------------------------|
| 1+24 LT to 2+75 LT | 2185 | - | 2185 | 12 |
| 2+94 LT to 4+47 LT | 1835 | - | 1835 | 18 |
| 4+80 LT to 8+44 LT | 4150 | - | 4150 | 24 |
| 0+80 RT to 1+01 RT | 240 | 240 | - | 6 |
| 1+25 RT to 2+75 RT | 1815 | - | 1815 | 12 |
| 2+95 RT to 4+46 RT | 1960 | 130 | 1830 | 18 |
| 4+80 RT to 8+43 RT | 4075 | - | 4075 | 24 |

TOTALS 16,260 370 15,890 114

BROWN AND ROBERTS, INC.
CONSULTING ENGINEERS & LAND SURVEYORS
1 WEST RIDGE ROAD HARRISBURG, IL 62946 (618) 252-8111



CITY OF WEST FRANKFORT
STREETSCAPE IMPROVEMENTS
SUMMARY OF QUANTITIES

Drawn By: *ECB* Checked By: *MWR*

Revisions
Item Date By

Scale: AS SHOWN Field Bk:

Job Number: 05-136 Date: 03/2007

Sheet

2

of 8