


FILE: Nw-qly.dwg  
 LAYOUT: Layout1  
 UPDATE BY: Jeremy Linke  
 SURVEY BOOK #  
 DATE: Thursday, April 03, 2008 11:22:53 AM  
 XREF DWG: tblint.dwg

REVISIONS		
NUMBER	BY	DATE



ITEM NUMBER	DESCRIPTION	UNIT	F/S/L QUANTITY	LOCAL ONLY QUANTITY	TOTAL QUANTITY	F/S/L RECORD QUANTITY	LOCAL ONLY RECORD QUANTITY	TOTAL RECORD QUANTITY
AR108504	APRON LIGHT POLE W/QUAD FIXTURE	EACH	3		3			
AR108030	1/C #3/O 600V UG CABLE	LF	500		500			
AR108088	1/C #6 XLP-USE	LF	3,400		3,400			
AR108090	1/C #10 XLP-USE	LF	3,000		3,000			
AR108158	1/C #8 5 KV UG CABLE IN UD	LF	5,082		5,082			
AR108752	1/C #2 GROUND	LF	150		150			
AR109120	ERECT ELECTRICAL TRANSCLOSURE	LS	1		1			
AR110213	3" STEEL DUCT, DIRECT BURY	LF	1,150		1,150			
AR110502	2-WAY CONCRETE ENCASED DUCT	LF	210		210			
AR110504	4-WAY CONCRETE ENCASED DUCT	LF	925		925			
AR110610	ELECTRICAL HANDHOLE	EACH	6		6			
AR110900	REMOVE DUCT	LF	240		240			
AR125100	ELEVATED RETROREFLECTIVE MARKER	EACH	16		16			
AR125415	MITL - BASE MOUNTED	EACH	32		32			
AR125442	TAXI GUIDANCE SIGN, 2 CHARACTER	EACH	2		2			
AR125444	TAXI GUIDANCE SIGN, 4 CHARACTER	EACH	1		1			
AR125902	REMOVE BASE MOUNTED LIGHT	EACH	8		8			
AR150510	ENGINEER'S FIELD OFFICE	LS	1		1			
AR150515	FIELD LABORATORY	LS	1		1			
AR150520	MOBILIZATION	LS	1		1			
AR150540	HAUL ROUTE	LS	1		1			
AR152410	UNCLASSIFIED EXCAVATION	CY	40,000		40,000			
AR152442	OFFSITE BORROW EXCAVATION	CY	81,000		81,000			
AR152540	SOIL STABILIZATION FABRIC	SY	49,045	755	49,800			
AR156510	SILT FENCE	LF	3,215		3,215			
AR156511	DITCH CHECK	EACH	15		15			
AR156520	INLET PROTECTION	EACH	30		30			
AR156531	EROSION CONTROL BLANKET	SY	68,600		68,600			
AR156540	RIPRAP	SY	250		250			
AR162410	CLASS E FENCE, VINYL - 10'	LF	1,670		1,670			
AR162620	CLASS E GATE - 20'	EACH	2		2			
AR162900	REMOVE CLASS E FENCE	LF	900		900			
AR162960	RELOCATE CLASS E FENCE	LF	2,400		2,400			
AR201610	BITUMINOUS BASE COURSE	TON	2,200	200	2,400			
AR208515	POROUS GRANULAR EMBANKMENT	CY	1,225		1,225			
AR209606	CRUSHED AGG. BASE COURSE - 6"	SY	3,850		3,850			
AR209608	CRUSHED AGG. BASE COURSE - 8"	SY	50,350	755	51,105			
AR401610	BITUMINOUS SURFACE COURSE	TON	1,924	121	2,045			
AR401650	BITUMINOUS PAVEMENT MILLING	SY	10,600		10,600			
AR401910	REMOVE & REPLACE BIT. PAVEMENT	SY	335		335			
AR501516	16" PCC PAVEMENT	SY	36,500		36,500			
AR501530	PCC TEST BATCH	EACH	1		1			
AR501910	REMOVE AND REPLACE PCC PAVEMENT	SY	20		20			
AR510515	GROUND ROD	EACH	22		22			
AR602510	BITUMINOUS PRIME COAT	GAL	4,580	230	4,810			
AR603510	BITUMINOUS TACK COAT	GAL	3,025	340	3,365			
AR620520	PAVEMENT MARKING - WATERBORNE	SF	9,310		9,310			
AR620525	PAVEMENT MARKING - BLACK BORDER	SF	5,350		5,350			
AR620900	PAVEMENT MARKING REMOVAL	SF	800		800			
AR701006	6" PVC STORM SEWER	LF	370		370			
AR701224	24" CMP	LF	190		190			

ITEM NUMBER	DESCRIPTION	UNIT	F/S/L QUANTITY	LOCAL ONLY QUANTITY	TOTAL QUANTITY	F/S/L RECORD QUANTITY	LOCAL ONLY RECORD QUANTITY	TOTAL RECORD QUANTITY
AR701512	12" RCP, CLASS IV	LF	567		567			
AR701518	18" RCP, CLASS IV	LF	486		486			
AR701524	24" RCP, CLASS IV	LF	195		195			
AR701530	30" RCP, CLASS IV	LF	115		115			
AR701536	36" RCP, CLASS IV	LF	228		228			
AR701542	42" RCP, CLASS IV	LF	341		341			
AR701548	48" RCP, CLASS IV	LF	698		698			
AR701572	72" RCP, CLASS IV	LF	1,380		1,380			
AR701900	REMOVE PIPE	LF	400		400			
AR705900	REMOVE UNDERDRAIN	LF	840		840			
AR705904	REMOVE UNDERDRAIN CLEANOUT	EACH	2		2			
AR751001	TRENCH DRAIN	LF	300		300			
AR751412	INLET - TYPE B	EACH	3		3			
AR751550	MANHOLE 5'	EACH	2		2			
AR751560	MANHOLE 6'	EACH	5		5			
AR751567	MANHOLE 7'	EACH	3		3			
AR751568	MANHOLE 8'	EACH	5		5			
AR751903	REMOVE MANHOLE	EACH	1		1			
AR752224	METAL END SECTION 24"	EACH	6		6			
AR752412	PRECAST REINFORCED CONC. FES 12"	EACH	4		4			
AR752472	PRECAST REINFORCED CONC. FES 72"	EACH	1		1			
AR752512	GRATING FOR CONC. FES 12"	EACH	4		4			
AR752572	GRATING FOR CONC. FES 72"	EACH	1		1			
AR752900	REMOVE END SECTION	EACH	5		5			
AR760301	1" WATER MAIN	LF	150		150			
AR770508	8" SANITARY SEWER	LF		1,218	1,218			
AR770700	SANITARY LIFT STATION	LS	1		1			
AR770704	SANITARY MANHOLE 4'	EACH	4	5	9			
AR800002	48" CCFRPP	LF	398		398			
AR800004	72" RCCP ELBOW	EACH	2		2			
AR800006	DUCKBILL CHECK VALVE	EACH	1		1			
AR800018	MAGNETIC FLOW METER AND VAULT	LS	1		1			
AR800020	BORING AND JACKING	LF	415		415			
AR800053	SOIL GUARD	SY	2,500		2,500			
AR800055	BITUMINOUS MILLING PLACEMENT	CY	1,300		1,300			
AR800060	AIR RELEASE VALVE AND VAULT	LS	1		1			
AR800070	TRAFFIC CONTROL AND PROTECTION	LS	1		1			
AR800072	12' X 12' BOX MANHOLE	EACH	1		1			
AR800073	7' X 12' BOX MANHOLE	EACH	3		3			
AR800090	7' X 15.5' BOX MANHOLE	EACH	1		1			
AR800094	DIVERSION STRUCTURE	LS	1		1			
AR800095	15" SANITARY SEWER	LF	1,450		1,450			
AR800096	10" FORCE MAIN	LF	2,890		2,890			
AR800126	STORM WATER SAMPLING EQUIPMENT	LS	1		1			
AR800131	STORM WATER SAMPLING BUILDING ELECTRICAL	LS	1		1			
AR800132	CHEMICAL/ELECTRICAL BUILDING MODIFICATIONS	LS	1		1			
AR800195	STORM WATER SAMPLING BUILDING	LS	1		1			
AR800196	BUILDING FOUNDATION AND FLOOR	LS	1		1			
AR901510	SEEDING	ACRE	26.0		26.0			
AR908510	MULCHING	ACRE	11.0		11.0			

**CHICAGO ROCKFORD INTERNATIONAL AIRPORT  
 ROCKFORD, ILLINOIS**

**SUMMARY OF QUANTITIES**

© Copyright CMT, Inc.

**CMT**  
 CRAWFORD, MURPHY & TILLY, INC.  
 CONSULTING ENGINEERS  
 License No. 184-000613

Chicago  
 Rockford  
 International  
 Airport

DESIGN BY:	ARR
DRAWN BY:	JRO
CHECKED BY:	CAL
APPROVED BY:	
DATE:	02/29/08
JOB No:	07258-06
ILLINOIS PROJECT: RFD-3787 A.I.P. PROJECT: 3-17-0088-XX <b>FINAL SUBMITTAL</b>	
SHEET 2 OF 83 SHEETS	