SUMMARY OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITIES	AS BUILT QUANTITIES
AR150510	ENGINEER'S FIELD OFFICE	L.S.	1	
AR152410	UNCLASSIFIED EXCAVATION	C.Y.	151	
AR152440	BORROW EXCAVATION	C.Y.	863	
AR209510	CRUSHED AGGREGATE BASE COURSE	TON	345	
AR401610	BITUMINOUS SURFACE COURSE	TON	227	
AR401665	BITUMINOUS PAVEMENT SAWING	L.F.	285	
AR602510	BITUMINOUS PRIME COAT	GAL.	337	
AR603510	BITUMINOUS TACK COAT	GAL.	142	
AR620520	PAVEMENT MARKING-WATERBORNE	S.F.	356	
AR701008	8" PVC STORM SEWER	L.F.	217	
AR751411	INLET-TYPE A	EACH	2	
AR752850	SPECIAL STRUCTURE	EACH	1	
AR901510	SEEDING	ACRE	0.3	
AR908510	MULCHING	ACRE	0.3	

INDEX TO SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	SUMMARY OF QUANTITIES AND INDEX TO SHEETS
3	PROPOSED SAFETY PLAN
4	PROPOSED CONSTRUCTION PLAN
5	PROPOSED DRAINAGE PLAN
6	PROPOSED STAKING PLAN
7	PROPOSED MARKING PLAN
8	PROPOSED NOTES AND DETAILS
9	PROPOSED CROSS-SECTIONS FOR HANGAR ACCESS TAXIWAY STA. 4+66.50 TO STA. 5+00
10	PROPOSED CROSS-SECTIONS FOR HANGAR ACCESS TAXIWAY STA. 5+25 TO STA. 6+00
11	PROPOSED CROSS-SECTIONS FOR HANGAR ACCESS TAXIWAY STA. 6+25 TO STA. 7+00
12	PROPOSED CROSS-SECTIONS FOR HANGAR ACCESS TAXIWAY STA. 7+25 TO STA. 7+75
13	PROPOSED CROSS-SECTIONS FOR HANGAR ACCESS TAXIWAY STA. 8+00 TO STA. 8+25

DATE	REVISION	BY

VANDALIA MUNICIPAL AIRPORT
VANDALIA, ILLINOIS

IL PROJ.: VLA-3724 A.I.P. PROJ.: 3-17-0102-810

HEI Project No. 07A0088D 0800
Filename R-002FLP.DWG
Scale NOT TO SCALE
Date 12/3/07

LAYOUT	BAK	12/3/07
DRAWN	BAK	12/3/07
REVIEWED	CAH	01/11/08

HANSON
Hanson Professional Services Inc.
1525 South Sixth Street
Springfield, Illinois 62703-2886
Offices Nationwide

CONSTRUCT HANGAR ACCESS TAXIWAY

SUMMARY OF QUANTITIES AND INDEX TO SHEETS

2

MAR 12, 2008 9:03 AM HAGL000382
I:\AIRPORTS\VANDALIA\07A0088\CAD\SHEETS\R-002FLP.DWG - FLAP