

•= SPECIALTY ITEMS, \*\* 80% FED, 10% STATE, 10% OP  
 OP=VILLAGE OF ORLAND PARK, OH=VILLAGE OF ORLAND HILLS,  
 TP=VILLAGE OF TINLEY PARK

URBAN

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY		LIGHTING		TRAFFIC SIGNALS 179TH	TRAFFIC SIGNALS 171ST	TRAFFIC SIGNALS 167TH	TRAFFIC SIGNALS 163RD	INTERCONNECT	NEW SIDEWALK/BIKE PATH	NEW SIDEWALK/BIKE PATH	NEW SIDEWALK/BIKE PATH	TINLEY PARK 100%	WATER MAIN/FIBER OPTIC/ EVP	WATER MAIN/SAN SEWER	RETAINING WALLS
				80% FED 20% STATE	100% OP	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	**	80% FED 20% STATE	80% FED 20% OP	80% FED 20% OH	80% FED 20% TP	100% TP	100% OP	100% TP	80% FED 20% STATE		
				0003	0021	0021	0021	0021	0021	0021	0021	0021	0028	0028	0028	0031	0043	0043	0040
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	372	372															
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	39	39															
20100500	TREE REMOVAL, ACRES	ACRE	0.25	0.25															
20101000	TEMPORARY FENCE	FOOT	4186	4186															
20200100	EARTH EXCAVATION	CU YD	43,586	43,586															
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	46,199	46,199															
20400800	FURNISHED EXCAVATION	CU YD	24,193	24,193															
20600200	GRANULAR EMBANKMENT, SPECIAL	CU YD	96															96	
20800150	TRENCH BACKFILL	CU YD	8610	8560														50	
* 21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	113975	113975															
* 21101685	TOPSOIL FURNISH AND PLACE, 24"	SQ YD	7028	7028															
* 25000210	SEEDING, CLASS 2A	ACRE	8.75	8.75															
* 25000310	SEEDING, CLASS 4	ACRE	3	3															
* 25000312	SEEDING, CLASS 4A	ACRE	3	3															
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1615	1615															

Rev. 4-16-13

Rev.

URS  
 100 S. WACKER DR.  
 SUITE 500  
 CHICAGO, IL 60606  
 TEL 312-939-4000  
 FAX 312-939-4098

FILE NAME * DIG0605-SHT-500.dgn	USER NAME * Frank.Stellone	DESIGNED -	REVISED -
SHT_PLAN	PLOT SCALE * 1/8"=1'-0"	DRAWN -	REVISED -
	PLOT DATE * 2/6/2013	CHECKED -	REVISED -
		DATE - 02/07/13	REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 1 OF 32 SHEETS STA. TO STA.

F.A.P. RATE. 330	SECTION 103R-3	COUNTY COOK	TOTAL SHEETS 932	SHEET NO. 5
CONTRACT NO. 60F05			ILLINOIS FED. AID PROJECT	