

\* = SPECIALTY ITEMS, \*\* 80% FED, 10% STATE, 10% OP  
 OP=VILLAGE OF ORLAND PARK, OH=VILLAGE OF ORLAND HILLS,  
 TP=VILLAGE OF TINLEY PARK

URBAN

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	LIGHTING	TRAFFIC SIGNALS 179TH	TRAFFIC SIGNALS 171ST	TRAFFIC SIGNALS 167TH	TRAFFIC SIGNALS 163RD	INTERCONNECT	NEW SIDEWALK /BIKE PATH	NEW SIDEWALK /BIKE PATH	NEW SIDEWALK /BIKE PATH	TINLEY PARK 100%	WATER MAIN/FIBER OPTIC/EVP	WATER MAIN/SAN SEWER	RETAINING WALLS
				80% FED 20% STATE 0003	100% OP 0021	80% FED 20% STATE 0021	80% FED 20% STATE 0021	80% FED 20% STATE 0021	** 0021	80% FED 20% STATE 0021	80% FED 20% OP 0028	80% FED 20% OH 0028	80% FED 20% TP 0028	100% TP 0031	100% OP 0043	100% TP 0043	80% FED 20% STATE 0040
* 81400300	DOUBLE HANDHOLE	EACH	10			2	3	3	2								
* 81603050	UNIT DUCT, 600V, 3-1C NO. 6, 1/C NO. 8 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	9652		9652												
* 81603060	UNIT DUCT, 600V, 3-1C NO. 8, 1/C NO. 10 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	100		100												
* 81603063	UNIT DUCT, 600V, 4-1C NO. 10, 1/C NO. 10 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	622		622												
* 81603081	UNIT DUCT, 600V, 3-1C NO. 2, 1/C NO. 4 GROUND, (XLP-TYPE USE), 1 1/2" DIA. POLYETHYLENE	FOOT	9652		9652												
* 81800300	AERIAL CABLE, 3-1/C NO. 2 WITH MESSENGER WIRE	FOOT	4050		4050												
* 82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	2		2												
* 82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	39		39												
* 83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	380		380												
* 83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	3		3												
* 84100110	REMOVAL OF TEMPORARY LIGHTING UNIT	EACH	32		32												
* 84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	39		39												
* 84200804	REMOVAL OF POLE FOUNDATION	EACH	42		42												
* 84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	2		2												
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2							2							

URS  
 100 S. WACKER DR.  
 SUITE 500  
 CHICAGO, IL 60606  
 TEL 312/333-9000  
 FAX 312/333-9000

Rev. 4-16-13

Rev.

FILE NAME : 016005-SHT-500.dgn	USER NAME : Frank.Stallone	DESIGNED -	REVISED -
SHT_PLAN	PLOT SCALE : 100.0000' / 1" =	DRAWN -	REVISED -
	PLOT DATE : 2/6/2013	CHECKED -	REVISED -
		DATE : 02/07/13	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 17 OF 32 SHEETS STA. TO STA.

F.A.P. RTE. 330	SECTION 103R-3	COUNTY COOK	TOTAL SHEETS 932	SHEET NO. 21
CONTRACT NO. 60F05			ILLINOIS FED. AID PROJECT	