


* = SPECIALTY ITEMS, ** 80% FED, 10% STATE, 10% OP
 OP=VILLAGE OF ORLAND PARK, OH=VILLAGE OF ORLAND HILLS,
 TP=VILLAGE OF TINLEY PARK

URBAN

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	LIGHTING	TRAFFIC SIGNALS 179TH	TRAFFIC SIGNALS 171ST	TRAFFIC SIGNALS 167TH	TRAFFIC SIGNALS 163RD	INTERCONNECT	NEW SIDEWALK /BIKE PATH	NEW SIDEWALK /BIKE PATH	NEW SIDEWALK /BIKE PATH	TINLEY PARK 100%	WATER MAIN/FIBER OPTIC/ EVP	WATER MAIN/SAN SEWER	RETAINING WALLS
				80% FED 20% STATE	100% OP	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	**	80% FED 20% STATE	80% FED 20% OP	80% FED 20% OH	80% FED 20% TP	100% TP	100% OP	100% TP	80% FED 20% STATE
				0003	0021	0021	0021	0021	0021	0021	0028	0028	0028	0031	0043	0043	0040
542A0247	PIPE CULVERTS, CLASS A, TYPE 1 42"	FOOT	292	292													
542A1069	PIPE CULVERTS, CLASS A, TYPE 2 24"	FOOT	604	604													
542A1075	PIPE CULVERTS, CLASS A, TYPE 2 30"	FOOT	284	284													
542A1081	PIPE CULVERTS, CLASS A, TYPE 2 36"	FOOT	255	255													
5421A012	PIPE CULVERTS, CLASS A, TYPE 1, 12" (TEMPORARY)	FOOT	895	895													
5421A024	PIPE CULVERTS, CLASS A, TYPE 1, 24" (TEMPORARY)	FOOT	46	46													
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	18	18													
54213666	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 21"	EACH	2	2													
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	6	6													
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	2	2													
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	297	297													
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	128	128													
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	201	201													
550A0160	STORM SEWERS, CLASS A, TYPE 1 36"	FOOT	252	252													



FILE NAME : D:\60F05-SHT-500.dgn
 USER NAME : Frank.Stallone
 DESIGNED -
 DRAWN -
 PLOT SCALE : 100.0000' / 1" =
 CHECKED -
 PLOT DATE : 2/6/2013
 DATE : 02/07/13

REVISIONS:
 REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 7 OF 32 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	103R-3	COOK	932	11
CONTRACT NO. 60F05			ILLINOIS FED. AID PROJECT	