

* = SPECIALTY ITEMS, ** 80% FED, 10% STATE, 10% OP
 OP=VILLAGE OF ORLAND PARK, OH=VILLAGE OF ORLAND HILLS,
 TP=VILLAGE OF TINLEY PARK

URBAN

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	LIGHTING	TRAFFIC SIGNALS 179TH	TRAFFIC SIGNALS 171ST	TRAFFIC SIGNALS 167TH	TRAFFIC SIGNALS 163RD	INTERCONNECT	NEW SIDEWALK /BIKE PATH	NEW SIDEWALK /BIKE PATH	NEW SIDEWALK /BIKE PATH	TINLEY PARK 100%	WATER MAIN/FIBER OPTIC/EVP	WATER MAIN/SAN SEWER	RETAINING WALLS
				80% FED 20% STATE	100% OP	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	**	80% FED 20% STATE	80% FED 20% OP	80% FED 20% OH	80% FED 20% TP	100% TP	100% OP	100% TP	80% FED 20% STATE
				0003	0021	0021	0021	0021	0021	0021	0028	0028	0028	0031	0043	0043	0040
56103100	DUCTILE IRON WATER MAIN 8"	FOOT	20	20													
56103200	DUCTILE IRON WATER MAIN 10"	FOOT	19	19													
56103300	DUCTILE IRON WATER MAIN 12"	FOOT	290	290													
56103400	DUCTILE IRON WATER MAIN 16"	FOOT	2706	2706													
56109210	WATER VALVES TO BE ADJUSTED	EACH	10	10													
56400400	FIRE HYDRANTS TO BE RELOCATED	EACH	1	1													
56400500	FIRE HYDRANTS TO BE REMOVED	EACH	13	11												2	
56400825	FIRE HYDRANT WITH AUXILIARY VALVE, VALVE BOX AND TEE	EACH	16	13												3	
59100100	GEOCOMPOSITE WALL DRAIN	SO YD	899														899
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	250	250													
60109510	PIPE UNDERDRAINS, FABRIC LINED TRENCH 4"	FOOT	7796	5296										2500			
60200105	CATCH BASINS, TYPE A, 4' -DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1													
60200805	CATCH BASINS, TYPE A, 4' -DIAMETER, TYPE B GRATE	EACH	2	2													
60201330	CATCH BASINS, TYPE A, 4' -DIAMETER, TYPE 23 FRAME AND GRATE	EACH	63	63													

00 S. WACKER DR.
 SUITE 500
 CHICAGO, IL 60606
 TEL (312) 539-0000
 FAX (312) 939-4998
URS

FILE NAME : 0160F05-SHT-500.dgn	USER NAME : Frank.Stallone	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE : 100.0000' / 1"	CHECKED -	REVISED -
	PLOT DATE : 2/6/2013	DATE : 02/07/13	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 9 OF 32 SHEETS STA. TO STA.

F.A.P. RTE. 330	SECTION 103R-3	COUNTY COOK	TOTAL SHEETS 932	SHEET NO. 13
CONTRACT NO. 60F05			Rev.	

ILLINOIS FED. AID PROJECT