

**= SPECIALTY ITEMS, ** 80% FED, 10% STATE, 10% OP
 OP=VILLAGE OF ORLAND PARK, OH=VILLAGE OF ORLAND HILLS,
 TP=VILLAGE OF TINLEY PARK

URBAN

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	LIGHTING	TRAFFIC SIGNALS 179TH	TRAFFIC SIGNALS 171ST	TRAFFIC SIGNALS 167TH	TRAFFIC SIGNALS 163RD	INTERCONNECT	NEW SIDEWALK /BIKE PATH	NEW SIDEWALK /BIKE PATH	NEW SIDEWALK /BIKE PATH	TINLEY PARK 100%	WATER MAIN/FIBER OPTIC/ EVP	WATER MAIN/SAN SEWER	RETAINING WALLS
				80% FED	100% OP	80% FED	80% FED	80% FED	**	80% FED	80% FED	80% FED	80% FED	100% TP	100% OP	100% TP	80% FED
				20% STATE		20% STATE	20% STATE	20% STATE		20% STATE	20% OP	20% OH	20% TP				20% STATE
				0003	0021	0021	0021	0021	0021	0021	0028	0028	0028	0031	0043	0043	0040
* 81400300	DOUBLE HANDHOLE	EACH	10			2	3	3	2								
* 81603050	UNIT DUCT, 600V, 3-1C NO. 6, 1/C NO. 8 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	9652		9652												
* 81603063	UNIT DUCT, 600V, 4-1C NO. 10, 1/C NO. 10 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	622		622												
* 81603081	UNIT DUCT, 600V, 3-1C NO. 2, 1/C NO. 4 GROUND, (XLP-TYPE USE), 1 1/2" DIA. POLYETHYLENE	FOOT	9652		9652												
* 81800300	AERIAL CABLE, 3-1/C NO. 2 WITH MESSENGER WIRE	FOOT	4050		4050												
* 82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	2		2												
* 82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	39		39												
* 83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	380		380												
* 83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	3		3												
* 84100110	REMOVAL OF TEMPORARY LIGHTING UNIT	EACH	32		32												
* 84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	39		39												
* 84200804	REMOVAL OF POLE FOUNDATION	EACH	42		42												
* 84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	2		2												
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2							2							

URS
 100 S. WACKER DR.
 SUITE 500
 CHICAGO, IL 60606
 TEL: (312) 851-4000
 FAX: (312) 939-4099

FILE NAME : D160P05-SHT-500.dgn	USER NAME : Frank.Stallone	DESIGNED -	REVISED -
		DRAWN -	REVISED -
		CHECKED -	REVISED -
SHT_PLAN	PLOT DATE : 2/6/2013	DATE - 02/07/13	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES			
SCALE:	SHEET 17 OF 32 SHEETS	STA.	TO STA.

F.A.P. RTE. 330	SECTION 103R-3	COUNTY COOK	TOTAL SHEETS 932	SHEET NO. 21
CONTRACT NO. 60F05				
ILLINOIS FED. AID PROJECT				

Rev-