SEE DRAWING PP-09
MATCH LINE STA. 69+50.00

MATCH LINE STA. 75+50.00
SEE DRAWING PP-11

COMB CONC CURB & GUTTER
TYPE B-6.24 (TYPICAL)

PORTLAND CEMENT CONCRETE
PAVEMENT, 10" (JOINTED)

LANDSCAPE MEDIAN
SEE LANDSCAPING PLANS

COMB CONC CURB & GUTTER
TYPE B-6.18 (MOD) TYPICAL

34.0'
17.0'
11.0'
34.0'

70+00 | 71 | 72 | US 45 (LAGRANGE RD) | 73 | 74 | 75+00

℄ US 45 (LaGRANGE RD)

PORTLAND CEMENT CONCRETE
PAVEMENT, 10" (JOINTED)

73+44.59
45.00' RT

74+21.02
45.00' RT

PORTLAND CEMENT CONCRETE
SIDEWALK, 5 INCH (5' WIDE)

6.0'

DC
20' R

73+64.18
63.24' RT

73+64.80
70.24' RT

25' R

+82.57
C.E.

1'

74+00.90
65.69' RT

5' R

74+01.18
73.68' RT

74+18.93
82.00' RT

74+86.50
64.00' RT

75+36.50
64.00' RT

PORTLAND CEMENT CONCRETE
SIDEWALK 5 INCH (5' WIDE)

6' PARKWAY

COMB CONC CURB & GUTTER
TYPE B-6.24 (TYPICAL)

74+02.29
76.87' RT

DIT

74+07.16
81.70' RT

74+19.02
90.00' RT

73+58.35
90.00' RT

73+60.98
85.87' RT

RETAINING WALL NO. 10
SEE STRUCTURAL PLANS
FOR DETAILS

LEGEND

= PARKING LOT PAVEMENT RESTORATION

= DETECTABLE WARNINGS SEE STANDARDS 424001, 424006, 424011, 424016, 424021, 424026, AND 424031 FOR DETAILS

PROPOSED PGL
SEE TYPICAL SECTIONS US 45

-1.71%

EXISTING GROUND LINE
℄ US 45

760	755	750	745	740	735
755.18	755.28				
754.16	754.42				
753.08	753.57				
751.90	752.71				
750.58	751.86				
749.23	751.00				
747.83	750.15				
746.46	749.29				
745.36	748.44				
744.36	747.58				
743.50	746.73				
742.87	745.87				
742.44	745.02				

69+50 | 70+00 | 70+50 | 71+00 | 71+50 | 72+00 | 72+50 | 73+00 | 73+50 | 74+00 | 74+50 | 75+00 | 75+50

PLAN: SURVEYED, PLOTTED, ADJUSTMENT CHECKED, RT. OF WAY CHECKED, CADD FILE NAME, NOTE BOOK, NO.____, BY, DATE

PROFILE: SURVEYED, PLOTTED, ADJUSTMENT CHECKED, BM. NOTED, STRUCTURE NOTATNS CHKD, NOTE BOOK, NO.____, BY, DATE

URS
100 S. WACKER DR.
SUITE 1500
CHICAGO IL 60606
TEL (312)939-1000
FAX (312)939-4198

FILE NAME = D160F05-SHT-PLNPRF10.dgn	USER NAME = Frank_Stallone	DESIGNED - JTF	REVISED -
		DRAWN - JTF	REVISED -
	PLOT SCALE = 40.0000 ' / in.	CHECKED - MJT	REVISED -
SHT_PLNPROF URBAN	PLOT DATE = 3/14/2013	DATE - 03/13/13	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PROPOSED PLAN AND PROFILE – US 45 (LAGRANGE ROAD)

SCALE:1"=20'H;1"=5'V | SHEET 10 OF 26 SHEETS | STA. 69+50.00 TO STA. 75+50.00

F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	103R-3	COOK	932	79
	PP-10	CONTRACT NO. 60F05		
		ILLINOIS FED. AID PROJECT		