

VILLAGE OF TINLEY PARK IDOT

NO.	ITEM DESCRIPTION	UNIT	TOTAL	63+00 TO 69+31	69+31 TO 75+92
1	EIGHT INCH CUT AND CAP	EACH	2	1	1
2	TWELVE INCH CUT AND CAP	EACH	1	1	0
3	TWLEVE INCH PLUG	EACH	1	0	1
4	DUCTILE IRON WATER MAIN, 6 INCH CLASS 52, WITH POLYETHYLENE ENCASEMENT, METHOD B	FOOT	20	15	5
5	DUCTILE IRON WATER MAIN, 8 INCH CLASS 52, WITH POLYETHYLENE ENCASEMENT, METHOD B	FOOT	40	20	20
6	DUCTILE IRON WATER MAIN, 12 INCH CLASS 52, WITH POLYETHYLENE ENCASEMENT, METHOD B	FOOT	1176	626	550
7	FIRE HYDRANTS TO BE REMOVED	EACH	4	2	2
8	FIRE HYDRANT WITH AUXILIARY VALVE, VALVE BOX AND TEE	EACH	5	3	2
9	6 INCH VALVE IN VALVE BOX	EACH	1	1	0
10	8 INCH X 8 INCH TAPPING SLEEVE AND VALVE IN 60 INCH DIAMETER VALVE VAULT, TYPE 1 FRAME, CLOSED LID	EACH	2	1	1
11	12 INCH X 12 INCH TAPPING SLEEVE AND VALVE IN 60 INCH DIAMETER VALVE VAULT, TYPE 1 FRAME, CLOSED LID	EACH	1	1	0
12	12 INCH BUTTERFLY VALVE IN 60 INCH VALVE VAULT, TYPE 1 FRAME AND CLOSED LID	EACH	1	0	1
13	REMOVE EXISTING WATER MAIN 12 INCH	FOOT	1176	626	550
14	ABANDON VALVE BOX	EACH	1	0	1
15	FIRE HYDRANT TO BE REMOVED AND SALVAGED	EACH	4	2	2
16	VALVE BASIN TO BE REMOVED	EACH	4	3	1
17	TRENCH BACKFILL	CU YD	87	50	37
18	DUCTILE IRON FITTINGS	POUND	1426	962	464
19	PCC SIDEWALK REMOVAL & REPLACEMENT	SQ FT	100	100	0
20	WATER SERVICE CONNECTION, 1.5" COMPLETE	EACH	1	1	0

WATER MAIN RELOCATION PLANS, SHEETS 1-5,
PREPARED UNDER MY DIRECT SUPERVISION.

Christopher J. King
 67-12871
 REGISTERED
 PROFESSIONAL
 ENGINEER
 STATE OF ILLINOIS
 LICENSE EXPIRES: 11/30/13

FILE NAME = 12600-QUAN-01 - IDOT P01	USER NAME =	DESIGNED - CJK	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	LAGRANGE ROAD WATER MAIN REPLACEMENT SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
	PLOT SCALE =	CHECKED -	REVISED -			330	103R-3	COOK	932	366	
	PLOT DATE =	DRAWN - RG	REVISED -			WM-01		CONTRACT NO. 60F05			
		DATE - 03/13/13	REVISED -			SCALE: NONE	SHEET NO. 1 OF 5 SHEETS	STA.	TO STA.		
						FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT			