


SUMMARY OF QUANTITIES		UNIT	URBAN 90% FED. 10% STATE TOTAL	CONSTRUCTION CODE				
CODE NO.	ITEM DESCRIPTION			0003 RDWY	0010 BRIDGE	0021 SIGNALS LIGHTING	0031 LNDSCP	0040 RET. WALL
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1			1		
* 86000300	MASTER CONTROLLER IN TYPE V CABINET	EACH	1			1		
* 86400100	TRANSCEIVER - FIBER OPTIC	EACH	4			4		
* 87000885	ELECTRIC CABLE ASSEMBLY IN CONDUIT, 600V (XLP-TYPE TC) 2/C NO. 6 AND NO. 8	FOOT	4,096			4,096		
* 87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	7,639			7,639		
* 87301125	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 12 3/C	FOOT	80			80		
* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	3,401			3,401		
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	3,402			3,402		
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	9,319			9,319		
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	4,637			4,637		
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	14,605			14,605		
* 87301727	ELECTRIC CABLE IN CONDUIT, COMMUNICATION NO. 19 6C	FOOT	3,566			3,566		

* SPECIALTY ITEM

 PATRICK ENGINEERING 4970 VARSITY DRIVE LISLE, IL 60532 patrickengr.com	USER NAME = kkooppen@rdwy.lisle PLOT CONFIG = PDFI@reg_3m011.plt PLOT SCALE = 1/16"=1' PLOT DATE = 2/18/2013 4:30:54 PM	DESIGNED - CPK DRAWN - MJP CHECKED - JAH DATE - 2/18/2013	REVISED - REVISED - REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION		SUMMARY OF QUANTITIES				F.A.U. RTE. 2746	SECTION 1616B	COUNTY COOK	TOTAL SHEETS 404	SHEET NO. 23
	SCALE: NA SHEET 500-20 OF 36 STA. TO STA.		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT		60J14									