

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	0005						
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	15	15					
25200110	SODDING, SALT TOLERANT	SO YD	15	15					
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SO YD	4	4					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	13	13					
40600300	AGGREGATE (PRIME COAT)	TON	66	66					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	25	25					
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), 1L-4.75, N50	TON	615	615					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	232	232					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	13.3	13.3					
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	0.5	0.5					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1386	1386					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	38	38					
44000154	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/4"	SO YD	1600	1600					
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	14900	14900					
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	4	4					

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES		CONSTRUCTION TYPE CODE 0005				
CODE NO	ITEM	UNIT	0005						
44000600	SIDEWALK REMOVAL	SO FT	38	38					
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SO YD	79	79					
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SO YD	50	50					
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SO YD	12.5	12.5					
50300300	PROTECTIVE COAT	SO YD	21	21					
60250200	CATCH BASINS TO BE ADJUSTED	EACH	1	1					
60266600	VALVE BOXES TO BE ADJUSTED	EACH	5	5					
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	5	5					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3					
67100100	MOBILIZATION	L SUM	1	1					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1					
70300100	SHORT TERM PAVEMENT MARKING	FOOT	895	895					
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	181.5	181.5					

FILE NAME: <i>16</i>	USER NAME: <i>gorenca/00</i>	DESIGNED: -	REVISED: -	<b>STATE OF ILLINOIS</b> <b>DEPARTMENT OF TRANSPORTATION</b>	US 6 / US 30 (CASS AVE) (MICHIGAN ST/MAYOR ART SCHULTZ DR. TO EAST OF CASSEDAY AVE) <b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE. 607	SECTION 2040-0406	COUNTY WILL	TOTAL SHEETS 20	SHEET NO. 3	
PLT SCALE: 1/4" = 100'	PLT DATE: 12/17/2012	DRAWN: -	REVISED: -			SCALE: _____	SHEET NO. _____ OF _____ SHEETS	STA. _____ TO STA. _____	CONTRACT NO. 60K97		
		CHECKED: -	REVISED: -			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT					
		DATE: -	REVISED: -								