

SUMMARY OF QUANTITIES			URBAN		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE 0005					
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	2711	2711					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	352	352					
21101600	TOPSOIL FURNISH AND PLACE, VARIABLE DEPTH	SO YD	3253	3253					
25000210	SEEDING, CLASS 2A	ACRE	0.672	0.672					
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	41	41					
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	41	41					
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	41	41					
25100630	EROSION CONTROL BLANKET	SO YD	3253	3253					
25200110	SODDING, SALT TOLERANT	SO YD	352	352					
25200200	SUPPLEMENTAL WATERING	UNIT	5	5					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	101	101					
40600300	AGGREGATE (PRIME COAT)	TON	502	502					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	189	189					
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	5111	5111					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					

SUMMARY OF QUANTITIES			URBAN		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE 0005					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	904	904					
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	12344	12344					
42001300	PROTECTIVE COAT	SO YD	704	704					
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	124434	124434					
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SO FT	36	36					
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SO YD	1082	1082					
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SO YD	1505	1505					
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SO YD	1317	1317					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	246	246					
60252800	CATCHBASINS TO BE RECONSTRUCTED	EACH	4	4					
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	7	7					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					

1

15

14

Rev. 4-8-13

FILE NAME *	USER NAME * paragon	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				US 6 (159TH ST.) SUMMARY OF QUANTITIES				F.A.P. RTE. 351	SECTION 3277 RS-4	COUNTY COOK	TOTAL SHEETS 32	SHEET NO. 3
CLIP WORK PLOT COPY FROM 2007 900 06250 ST plot.dgn	PLOT SCALE * 100000' / in	DRAWN -	REVISED -									CONTRACT NO. 60K98				
	PLOT DATE * 12/26/2012	CHECKED -	REVISED -													
		DATE -	REVISED -													