

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		100% STATE 0005					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	167	167					
25200110	SODDING, SALT TOLERANT	SO YD	167	167					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	13	13					
40600300	AGGREGATE (PRIME COAT)	TON	63	63					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	40	40					
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	496	496					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	69	69					
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SO YD	657	657					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	8	8					
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	70	70					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1382	1382					

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		100% STATE 0005					
42001300	PROTECTIVE COAT	SO YD	130	130					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	1357	1357					
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SO YD	460	460					
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SO FT	497	497					
44022029	PARTIAL DEPTH REMOVAL 3"	SO YD	412	412					
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	142	142					
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	108	108					
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SO YD	150	150					
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	10	10					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
	* SPECIALTY ITEMS								

FILE NAME *	USER NAME * rdd/kuama	DESIGNED -	REVISED -
CHW_wolfroadharrisonstreettoilrte38(000001)11-11-11.dwg		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**WOLF ROAD - HARRISON STREET TO IL RTE 38 (ROOSEVELT ROAD)
SUMMARY OF QUANTITIES**

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2689	(3185 & 3186) RS-3	COOK	20	3
CONTRACT NO. 60M30			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT	

SCALE:	SHEET NO.	OF	SHEETS	STA.	TO	STA.
--------	-----------	----	--------	------	----	------