SUMMARY OF QUANTITIES

100% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE ROADWAY 0005	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	84	84	
20400800	FURNISHED EXCAVATION	CU YD	180	180	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	395	395	
25000210	SEEDING, CLASS 2A	ACRE	0.25	0.25	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	23	23	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	23	23	
25100630	EROSION CONTROL BLANKET	SQ YD	1,210	1,210	
25200110	SODDING, SALT TOLERANT	SQ YD	77	77	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	40	40	
40600300	AGGREGATE (PRIME COAT)	TON	240	240	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	46	46	
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2,387	2,387	
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	333	333	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	5,156	5,156	
42001300	PROTECTIVE COAT	SQ YD	41	41	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	59,590	59,590	
44201811	CLASS D PATCHES, TYPE I, 14 INCH	SQ YD	55	55	
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SQ YD	460	460	
44201819	CLASS D PATCHES, TYPE III, 14 INCH	SQ YD	580	580	
44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SQ YD	470	470	
48101620	AGGREGATE SHOULDERS, TYPE B 10"	SQ YD	45	45	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	500	500	
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	1	1	
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	3	3	
60404950	FRAMES AND GRATES, TYPE 24	EACH	1	1	
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	5	5	
63100167	TRAFFIC BARRIER TERMINAL, TYPE I (SPECIAL) TANGENT	EACH	3	3	
63200310	GUARDRAIL REMOVAL	FOOT	150	150	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5	
67100100	MOBILIZATION	L SUM	1	1	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	5,634	5,634	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1,241	1,241	

35

100% STATE

	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE ROADWAY 0005	
	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	116,317	116,317	
	70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	7,671	7,671	
	70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	1,816	1,816	
	70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	4,284	4,284	
	70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	723	723	
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	50,790	50,790	
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1,241	1,241	
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	58,158	58,158	
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3,836	3,836	
*	78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	908	908	
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2,142	2,142	
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	362	362	
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	613	613	
*	78200420	GUARDRAIL MARKERS, TYPE B	EACH	12	12	
*	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	3	3	
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	613	613	
*	88600600	DETECTOR LOOP REPLACEMENT	FOOT	1,150	1,150	
	X2020110	GRADING AND SHAPING SHOULDERS	UNIT	300	300	
	X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	18	18	
	Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	230	230	
	Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4	
	Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	

22

* SPECIALTY ITEMS