

CODE NO.	ITEM	UNIT	CONSTR. CODE	
			URBAN 100% STATE TOTAL QUANTITY	0005 ROADWAY RURAL
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	27	27
40600300	AGGREGATE (PRIME COAT)	TON	130	130
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	3	3
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1342	1342
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	252	252
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	2732	2732
42001300	PROTECTIVE COAT	SQ YD	2	2
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	32513	32513
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	10	10
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SQ FT	7557	7557
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	20	20
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	650	650
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	300	300
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	480	480

CODE NO.	ITEM	UNIT	CONSTR. CODE	
			URBAN 100% STATE TOTAL QUANTITY	0005 ROADWAY RURAL
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	744	744
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	1	1
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	10	10
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2146	2146
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	110	110
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	38452	38452
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	463	463
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	150	150
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	74	74
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	110	110

* - SPECIALTY ITEM

FILE NAME *	USER NAME = <i>amrmpfer</i>	DESIGNED - RG	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	US ROUTE 45 (MCHENRY ROAD) SUMMARY OF QUANTITIES			F.A.P. RTE. 872	SECTION 41-RS-4	COUNTY LAKE	TOTAL SHEETS 22	SHEET NO. 3
	PLOT SCALE = 100.0000 "/td> <td>DRAWN - RG</td> <td>REVISED -</td> <td>SCALE:</td> <td>SHEET NO.</td> <td>OF</td> <td>SHEETS</td> <td>STA.</td> <td>TO STA.</td> <td colspan="2">ILLINOIS FED. AID PROJECT</td>	DRAWN - RG	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT	
	PLOT DATE = 9/28/2012	CHECKED - MGR	REVISED -								CONTRACT NO. 60N29	
		DATE - 9/28/2012	REVISED -									