URBAN

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		100% STATE 0005					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	35	35					
25200110	SODDING, SALT TOLERANT	SQ YD	35	35					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	15	15					
40600300	AGGREGATE (PRIME COAT)	TON	75	75					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	29	29					
40600827	POLYMERIZED LEVELING BINDER	TON	941	941					
	(MACHINE METHOD), IL-4.75, N50								
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT	SQ YD	167	167					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	115	115					
40603335	HOT-MIX ASPHALT SURFACE COURSE,	TON	2131	2131					
	MIX "D", N50								
42001300	PROTECTIVE COAT	SQ YD	79	79					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	51	51					
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	925	925					
* SPECIALTY	ITEMS								

URBAN

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		100% STATE 0005					
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	18095	18095					
44000600	SIDEWALK REMOVAL	SQ FT	51	51					
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	681	681					
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	428	428					
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	238	238					
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	191	191					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	342	342					
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	3	3					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70102620	TRAFFIC CONTROL AND PROTECTION,	L SUM	1	1					
	STANDARD 701501								
70102635	TRAFFIC CONTROL AND PROTECTION,	L SUM	1	1					
	STANDARD 701701								
70300100	SHORT TERM PAVEMENT MARKING	FOOT	1980	1980					
* SPECIALTY	ITEMS								

FILE NAME = c:\pw_work\pw168\pencept\d0257f27\D3371-sht-plan.dgn	USER NAME = pencept	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 12/20/2012	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

HARRISON STREET-ILL 38 (ROOSEVELT ROAD) TO WOLF ROAD
SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1427	3205B-RS-1	COOK	22	3
		CONTRACT NO. 60N67		

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT