SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		0005					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	48	48					
40600300	AGGREGATE (PRIME COAT)	TON	113	113					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	300	300					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	3590	3590					
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	7438	7438					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	4761	4761					
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	16028	16028					
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	308	308					
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	449	449					
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	16757	16757					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1935	1935					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4					
67100100	MOBILIZATION	L SUM	1	1					
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1					

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		0005					
70300100	SHORT TERM PAVEMENT MARKING	FOOT	2438	2438					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	55739	55739					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	121	121					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	18580	18580					
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	55739	55739					
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	121	121					
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	389	389					
78300100	PAVEMENT MARKING REMOVAL	SQ FT	18620	18620					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	377	377					
LR400510	REJUVENATING AGENT	GALLON	5430	5430					
X2020110	GRADING AND SHAPING SHOULDERS	UNIT	429	429					
Z0010619	HOT IN-PLACE RECYCLING	SQ YD	53127	53127					
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	257	257					

*Specialty Items

FILE NAME : c:\dpw_work\pwidot\pyirzorawski\d0285808\D134111sht_plan.dgn	USER NAME : pyirzorawski	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / In.	CHECKED -	REVISED -
	PLOT DATE = 1/14/2013	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

MANHATTAN–MONEE ROAD (SCHOOLHOUSE RD. TO CENTER RD.)
SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
531	40X-RS-9	WILL	18	3
		CONTRACT NO. 60N71		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

D134111sht_plan.dgn 1/14/2013 10:40:21 AM User:pyrzorawski