


CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				100% STATE	
				ROADWAY	URBAN
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	383	383	
25200110	SODDING, SALT TOLERANT	SO YD	383	383	
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SO YD	71	71	
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SO YD	15	15	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	69	69	
40600300	AGGREGATE (PRIME COAT)	TON	341	341	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	179	179	
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	3,514	3,514	
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	885	885	
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SO YD	2,010	2,010	
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	882	882	
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	10	10	
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	8,419	8,419	
42001300	PROTECTIVE COAT	SO YD	1,725	1,725	

2

• SPECIALTY ITEMS

Rev. 4-11-13

COMPANY NAME: HRGreen  
 PROJECT CONTACT: HRGreen.com  
 CLIENT: HRGreen.com  
 DATE PLOTTED: 2/6/2013 9:43:51 AM  
 FILE NAME: 86000985-15-sum-01.dwg  
 PLOT DRIVER: acadprt  
 PEN TABLE: s:\bids\01\trans.tbl



USER NAME = spenal	DESIGNED - CMH	REVISED -
	DRAWN - SMP	REVISED -
PLOT SCALE = N/A	CHECKED - TEH	REVISED -
PLOT DATE = 2/6/2013	DATE - 2/6/13	REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N/A SHEET NO. 1 OF 5 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
348	2011-080-RS	COOK	44	3
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 60R07	