


CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				100% STATE	
				ROADWAY	
				0005	
				URBAN	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	28,900		28,900
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3,970		3,970
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	580		580
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	3,760		3,760
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	420		420
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	430		430
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	2,083		2,083
A X4060120	NON-TRACKING BITUMINOUS MATERIALS (PRIME COAT)	POUND	55,855		55,855
X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	1,560		1,560
X5537800	STORM SEWERS TO BE CLEANED 12"	FOOT	2,400		2,400
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	179		179
X6060500	CORRUGATED MEDIAN REMOVAL	SO FT	985		985
X7043900	PREFORMED JOINT FILLER REMOVAL	FOOT	9,000		9,000
Z0038123	PORTLAND CEMENT CONCRETE SURFACE REMOVAL 2 1/2"	SO YD	798		798
Z0004562	COMBINATION CONCRETE CURB & GUTTER REMOVAL AND REPLACEMENT	FOOT	4,164		4,164
Z0017800	DRAINAGE & UTILITY STRUCTURES TO BE RECONSTRUCTED (SPECIAL)	EACH	5		5

* SPECIALTY ITEMS

A Rev. 4-11-13

COMPANY NAME: HRGreen.com
 PROJECT CONTACT: spornol
 CLIENT: HRGreen
 DATE PLOTTED: 2/6/2013 9:44:02 AM
 FILE NAME: 600018-15-sum-00.dgn
 PLOT DRIVER: plotter
 PLOT SCALE: N/A
 PLOT DATE: 2/6/2013



USER NAME = spornol	DESIGNED - CMH	REVISED -
	DRAWN - SMP	REVISED -
	CHECKED - TEH	REVISED -
	DATE - 2/6/13	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES			
SCALE: N/A	SHEET NO. 4 OF 5 SHEETS	STA.	TO STA.

F.A.P. RTE. 348	SECTION 2011-080-RS	COUNTY COOK	TOTAL SHEETS 44	SHEET NO. 6
CONTRACT NO. 60R07			ILLINOIS FED. AID PROJECT	