

94

SUMMARY OF QUANTITIES				CONSTRUCTION CODE	
CODE NO	ITEM	UNIT	TOTAL QUANTITY	0014	
				100% STATE	
20200100	EARTH EXCAVATION	CU YD	442	442	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	1,982	1,982	
25000210	SEEDING, CLASS 2A	ACRE	0.1	0.1	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	9	9	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	9	9	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	9	9	
25100630	EROSION CONTROL BLANKET	SO YD	1,982	1,982	
30300112	AGGREGATE SUBGRADE IMPROVEMENT, 12"	SO YD	368	368	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1	1	
40600300	AGGREGATE (PRIME COAT)	TON	14	14	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	1,112	1,112	
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	157	157	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	183	183	
40603590	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N70	TON	612	612	

SPECIALTY ITEM *

FILE NAME: 0160602-shl-500.dgn
 USER NAME: JDDT
 PLOT SCALE: 108.0000' / IN.
 PLOT DATE: 1/16/2013



CHRISTIAN-ROGE & ASSOCIATES, INC.
 ENGINEERS-PLANNERS-SURVEYORS
 211 WEST WACKER DRIVE
 CHICAGO, ILLINOIS 60606
 PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED - S.J.P.
 DRAWN - A.C.S.
 CHECKED - M.P.
 DATE - JANUARY 17, 2013

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
 I-55

SCALE: NONE SHEET NO. 1 OF 7 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	87B, D-BR-1	WILL	106	3
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60R62	