

AGGREGATE SUBGRADE IMPROVEMENT, 12" SCHEDULE		
LOCATION		SQ YD
STA. 1118+00 TO STA. 1123+40	S. B. INSIDE SHOULDER	120
STA. 1118+00 TO STA. 1123+40	N. B. INSIDE SHOULDER	120
STA. 1259+13 TO STA. 1262+02	S. B. INSIDE SHOULDER	64
STA. 1259+13 TO STA. 1262+02	N. B. INSIDE SHOULDER	64
TOTAL		368

EARTH EXCAVATION SCHEDULE		
LOCATION		EARTH EXCAVATION CU YD
STA. 1118+00 TO STA. 1123+40	S. B. INSIDE SHOULDER	120
STA. 1118+00 TO STA. 1123+40	N. B. INSIDE SHOULDER	120
STA. 1259+13 TO STA. 1262+02	S. B. INSIDE SHOULDER	64
STA. 1259+13 TO STA. 1262+02	N. B. INSIDE SHOULDER	64
STA. 1120+60 TO STA. 1123+40	N. B. INSIDE SHOULDER	31
STA. 1258+00 TO STA. 1261+85	S. B. INSIDE SHOULDER	43
TOTAL		442

FILLING INLETS, SPECIAL SCHEDULE		
LOCATION	FILLING INLETS, SPECIAL	
	EACH	
STA. 1261+93, S. B. OUTSIDE SHLD	1	
STA. 1261+93, S. B. INSIDE SHLD	1	
STA. 1123+07, S. B. OUTSIDE SHLD	1	
STA. 1123+07, S. B. INSIDE SHLD	1	
TOTAL		4

REPLACEMENT REFLECTORS		
LOCATION	REPLACEMENT REFLECTORS	
	EACH	
NORTHBOUND		
STA. 1070+00 TO STA. 1105+00	90	
SOUTHBOUND		
STA. 1212+00 TO STA. 1262+00	127	
TOTAL		217

HOT-MIX ASPHALT PAVING SCHEDULE						
LOCATION	POLY HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	POLY HOT-MIX ASPHALT SURFACE CRS, MIX "F", N90	HOT-MIX ASPHALT SHOULDERS, 6"	HOT-MIX ASPHALT SHOULDERS, 12"	
	TON	TON	TON	SQ YD	SQ YD	
STA. 1123+00, S. B.	37	64	41			
STA. 1123+00, N. B.	38	28	42			
STA. 1261+50, S. B.	41	62	46			
STA. 1261+50, N. B.	41	29	46			
NORTH MEDIAN CROSSOVER			315			
STA. 1120+28 TO STA. 1275+67, RT(NB)				134		
STA. 1262+02 TO STA. 1258+78, RT(SB)				156		
STA. 1118+00 TO STA. 1123+00, LT(SB)					334	
STA. 1118+00 TO STA. 1123+40, LT(NB)					360	
STA. 1261+87 TO STA. 1259+13, RT(SB)					184	
STA. 1261+46 TO STA. 1259+14, LT(NB)					155	
TOTAL		157	183	490	290	1,033

HOT-MIX ASPHALT REMOVAL SCHEDULE				
LOCATION		HMA SURFACE REM, 1 1/2"	HMA SURFACE REM, 1 3/4"	HMA SURFACE REM, 2 1/4"
		SQ YD	SQ YD	SQ YD
STA. 1095+75 TO STA. 1123+33	S. B.	766		
STA. 1261+85 TO STA. 1250+00	S. B.	329		
STA. 1097+00 TO STA. 1123+60	N. B.	739		
STA. 1261+45 TO STA. 1249+00	N. B.	346		
NORTH MEDIAN CROSSOVER			3,219	
STA. 1122+83 TO STA. 1123+33	S. B.			166
STA. 1123+05 TO STA. 1123+55	N. B.			168
STA. 1262+12 TO STA. 1262+62	S. B.			177
STA. 1261+61 TO STA. 1261+11	N. B.			177
TOTAL		2,180	3,219	688

HIGH TENSION CABLE SCHEDULE		
LOCATION	HIGH TENSION CABLE MEDIAN BARRIER TERMINALS	HIGH TENSION CABLE MEDIAN BARRIER
	EACH	FOOT
STA. 1118+00	1	
STA. 1118+00 TO STA. 1121+25		325
STA. 1121+25	1	
STA. 1261+75	1	
STA. 1261+75 TO STA. 1257+00		475
STA. 1257+00	1	
TOTAL		800

HOT-MIX ASPHALT SURFACE REMOVAL BUTT JOINT		
LOCATION		HOT-MIX ASPHALT SURFACE REM, BUTT JT
		SQ YD
STA. 1122+13 TO STA. 1122+83	S. B.	253
STA. 1122+35 TO STA. 1123+05	N. B.	261
STA. 1261+42 TO STA. 1262+12	S. B.	299
STA. 1260+41 TO STA. 1261+11	N. B.	299
TOTAL		1,112

FILE NAME = D160R62-sht-schedule1.dgn
 USER NAME = IDOT
 PLOT SCALE = 100.0000' / IN.
 PLOT DATE = 1/18/2013



DESIGNED - S.J.P.	REVISED -
DRAWN - A.C.S.	REVISED -
CHECKED - M.P.	REVISED -
DATE - JANUARY 17, 2013	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
 I-55

SCALE: NONE SHEET NO. 1 OF 2 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	87B, D-BR-1	WILL	106	10
CONTRACT NO. 60R62				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				