



*Width of Joint may vary as required by Joint manufacturer
 **Cost Included with Concrete Removal

Note "A"
 Drill & epoxy grid reinforcement bars according to Article 584 of the Standard Specifications. Cost included with Concrete Superstructure

Note:
 Existing reinforcement bars shall be cleaned and incorporated into the new construction. Cost included with Concrete Removal

FILE NAME: I:\113\113-1-55 over Dwg Files\Struct\113\113-1-55.dwg

	USER NAME = 1007	DESIGNED = J.C.N./B.N.S./J.W.	REVISED =	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	EXPANSION JOINT RECONSTRUCTION AT I13-NORTHBOUND-II STRUCTURE NO. 099-0009	F.A.I. / R.T.E. = 55	SECTION = 87B, D-BR-1	COUNTY = WILL	TOTAL SHEETS = 106	SHEET NO. = 66
	PLOT SCALE = 5/8" = 1' / 1/4" PLOT DATE = 3/19/2013	CHECKED = B.N.S./J.W. DRAWN = F.M. DATE = MARCH 20, 2013	REVISED = REVISED = REVISED =			SHEET NO. 527 OF 560 SHEETS	CONTRACT NO. 60662 ILLINOIS FED. AID PROJECT			