

				CONSTRUCTION TYPE CODE 100% STATE																				
CODE		UNIT	TOTAL	ROADWAY 0004	BRIDGE 0014	BRIDGE 0014	BRIDGE 0014	BRIDGE 0014	BRIDGE 0014	BRIDGE 0014	BRIDGE 0014	BRIDGE 0014	BRIDGE 0014	BRIDGE 0014	BRIDGE 0014	BRIDGE 0014	BRIDGE 0014	BRIDGE 0014	BRIDGE 0014	BRIDGE 0014	BRIDGE 0014	BRIDGE 0014	BRIDGE 0014	
NO.	ITEM		QUANTITY	URBAN	016-2574	016-0111 016-0112	016-0113 016-0114	016-0115 016-0116	016-0117 016-0118	016-0120 016-1109	016-0121 016-0122	016-0123 016-1071	016-0124 016-1074 016-1077	016-0125 016-1073 016-1078	016-0127	016-2654	016-0128	016-0129	016-0130	016-0131	016-0132	016-0133	016-0134	016-0135
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	18	18																				
X8210305	PROTECTION AND MAINTENANCE OF EXISTING UNDERPASS LIGHTING	I. SUM	1			0.25			0.25			0.25										0.25		
Z001905	STRUCTURAL STEEL REPAIR	POUND	3310																			3310		
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	17191			130			231			205				141						16484		
Z0012755	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQ FT	278																			278		
Z0021906	SILICONE JOINT SEALER, 1.5"	FOOT	229.0																			229.0		
Z0021907	SILICONE JOINT SEALER, 1.75"	FOOT	485							136.5								42.5				142	164	
Z0021908	SILICONE JOINT SEALER, 2"	FOOT	1618.0			102.0	72.0		84.0		72.0	78.0	12.0	18.0	30.0		30.0	24.0		12.0	48.0	684.0		
Z0021912	SILICONE JOINT SEALER, 2.5"	FOOT	264		6.0									30.0	78.0	48.0				42.0	60.0			
Z0021918	SILICONE JOINT SEALER, 4"	FOOT	222.0					24.0							78.0			72.0				48.0		
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	208			52			52			52										52		
Z0041895	POLYMER CONCRETE	CU FT	312.3	135.0	1.9	8.5	6.0	2.0	7.0	7.0	6.0	6.5	1.6	4.9	9.0	6.5	6.5	8.0	3.0	4.5	9.0	61.0	6.5	12.5
Z0073200	TEMPORARY SHORING AND CRIBBING	EACH	398						5													393		
© Z0076004	TRAINEES-TRAINING PROGRAM GRADUATE	Hour	1000	1000																				

Z0021902 SILICONE JOINT SEALER FOOT 42 42

Z0021910 SILICONE JOINT SEALER FOOT 222 24 78 72 48

X0327596 PRECAST PRESTRESSED CONCRETE I-BEAM REPAIR I. SUM 1 1

© 0042



DESIGNED - RG	REVISED -
DRAWN - RG	REVISED -
CHECKED - MR	REVISED -
DATE - DECEMBER 2012	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.I. RTE. 90/94	SECTION 2012-055BR	COUNTY COOK	TOTAL SHEETS 107	SHEET NO. 5
CONTRACT NO. 60V58			ILLINOIS FED. AID PROJECT	

Rev.