

MILE MARKER	DIRECTION	LANE	LENGTH (FT)	WDTH (FT)	PATCH AREA				SAWCUTS 44213200 (FT)	TIE BARS ZD075300 (EACH)	PATCHING REINFORCEMENT 44213000 (SQ YD)	PCC SURFACE REMOVAL (VARIABLE DEPTH) X4400100 (SQ YD)	POLYMER CONCRETE Z0041895 (CU FT)
					TYPE I (SQ YD)	TYPE II (SQ YD)	TYPE III (SQ YD)	TYPE IV (SQ YD)					
42-62	SB	1	50	12				66.7	205.0	50	66.7		
43-54 TO 43-57	SB	2	8	6		5.3			47.0		5.3		
44-69 TO 44-15	SB	2	6	12		8.0			67.0		8.0		
44-15 TO 44-20	SB	4,5	50	12				66.7	205.0	50	66.7		
44-15 TO 44-20	SB	4,5	12	15			20.0		103.0		20.0		
44-33 TO 44-41	SB	3	12	12			16.0		79.0		16.0		
44-33 TO 44-41	SB	4	12	12			16.0		91.0		16.0		
44-33 TO 44-41	SB	5	12	12			16.0		91.0		16.0		
44-33 TO 44-41	SB	4,5	5	12		6.7			70.0		6.7		
44-96 TO 45-11	SB	3	50	12				66.7	155.0	50	66.7		
44-96 TO 45-11	SB	3	50	12				66.7	155.0	50	66.7		
45-05	SB	1	6	12		8.0			73.0		8.0		
45-15	SB	3	8	6		5.3			47.0		5.3		
45-58	SB	2	6	12		8.0			67.0		8.0		
45-58	SB	3	6	12		8.0			67.0		8.0		
45-68	SB	SHOULDER	12	25				33.3	131.0		33.3		
46-00	SB	4	12	12			16.0		91.0		16.0		
46-55 TO 46-68	SB	3	6	12		8.0			67.0		8.0		
46-68 TO 46-72	SB	3	6	12		8.0			67.0		8.0		
46-68 TO 46-72	SB	4	12	12			16.0		91.0		16.0		
46-72 TO 46-83	SB	3	50	12				66.7	155.0	50	66.7		
46-72 TO 46-83	SB	4	50	12				66.7	205.0	50	66.7		
47-42	SB	1	6	12		8.0			73.0		8.0		
47-42	SB	3	6	12		8.0			67.0		8.0		
47-42	SB	4	6	12		8.0			73.0		8.0		
47-42	SB	4	6	12		8.0			73.0		8.0		
47-47 TO 47-75	SB	RAMP	15	18				30.0	124.0		30.0		
47-75 TO 47-78	SB	3	50	12				66.7	155.0	50	66.7		
48-28 TO 48-50	SB	RAMP	12	20				26.7	123.0		26.7		
49-20 TO 49-39	SB	4	6	12		8.0			73.0		8.0		
49-80 TO 49-16	SB	4	6	6	4.0				49.0		4.0		
SHEET TOTALS					4.0	105.3	100.0	556.7	3139.0	350.0	766.0	0.0	0.0
					SQ YD	SQ YD	SQ YD	SQ YD	FT	EACH	SQ YD	SQ YD	CU FT



USER NAME =	DESIGNED - RG	REVISED -
DRAWN - RG	REVISED -	
CHECKED - MR	REVISED -	
DATE - DECEMBER 2012	REVISED -	

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**PATCHING LOCATIONS
SB**

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.I. RTE. 90/94	SECTION 2012-055BR	COUNTY COOK	TOTAL SHEETS 107	SHEET NO. 13
CONTRACT NO. 60V58				ILLINOIS FED. AID PROJECT